

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer
Civil Maintenance Division
Dhaka WASA, Dhaka
6th floor, WASA Bhaban
98 Kazi Nazrul Islam avnue, Dhaka.

④

Name of the Work: Supplying, fitting & fixing of CI sheet with false ceiling (damaged portion) and related repairing works of inner wall at Mirpur Shewrapara tin-shed WASA Staff Quarter.

Item No.	Group	PWD 2022	Description of Items of Works	Unit	Quantity	Unit rates or prices	Amount
1	Civil	15.1.1	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	sqm	58.852	299.001	17,596.807
2	Civil	16.2.1	Interior standard acrylic emulsion paint (plastic or matt finish) of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container; applying to interior wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary interior sealer of specified brand on prepared surface; then applying necessary interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of interior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	sqm	169.268	258.001	43,671.313
3	Civil	16.3.2	Premium synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in two coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	sqm	46.840	238.001	11,147.967
4	Civil	11.1.2.1	Supplying and making door and window frames (Chowkat) for all floors in/c wall side grove cutting, moulding by CNC machine or any other means with matured seasoned wood of required size including painting two coats of coal tar to the surface in contact with wall, fitting and fixing in position etc. all complete and accepted by the Engineer-in-charge. (All sizes of wood are finished).	cmu	0.100	145620.001	14,562.000

[Signature]

[Signature]

[Signature]

	Civil	12.1.2.2	Supplying, fitting and fixing of 38 mm thick well matured seasoned (moisture content should be between 12% to 16%) solid wood single leaf door shutter having stile section 100mm x 38mm, top rail section 125mm x 38mm, lock rail section 100mm x 38mm and bottom rail section 225mm x 38mm (made from minimum 250mm wide plank) with 4nos 100mm long, 3mm thick hinge, 12mm dia 250mm long tower bolt, 12mm dia 200mm long socket bolt, 2nos 150mm long handle, hinged cleats and buffer blocks. All complete in all floors and accepted by the Engineer-in-charge. (All sizes of wood are finished)	sqm	7.804	8296.001	64,741.992
6	Civil	18.2.1.2	Supplying, fitting and fixing 12 mm thick burma teak (BT) veneered board/ ply board/ particle board in walling with best quality and well seasoned garjan wood frame of section of 50 mm x 25 mm at 600 mm x 600 mm in grid, including grove where necessary, fitted and fixed to wall by plugs, nails, screws etc. maintaining leveled and finished exposed faces including. making holes in wall and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, electricity, accessories, labour for installation, scaffolding, screws, nails etc. All complete as per design, approved sample and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type). 12 mm thick BT ply board walling	sqm	3.902	3098.001	12,088.400
7	Sanitary	26.12.4	Supplying, fitting and fixing of country made glazed vitreous W/H wash basin excluding pedestal. The sanitary ware shall conform BDS1162:2014. The glaze shall be thoroughly fused to body. The minimum thickness of body at any section shall be 5 mm. When assembled together and when examined from a distance of 60 cm, the outer surface shall not show to the unaided eye, blemishes or defects in excess of those listed in BDS standard. The mean value of water absorption shall not be greater than 0.5% of the ware when dry. When tested with chemical solutions The materials used for making glaze shall not contain lead compound. In case of certain coloring oxides used for making colored glaze, the lead content, if any, shall not exceed 5 percent of the weight of the glaze materials. Appliances shall be clearly and indelibly marked at a prominent place, visible even after the appliances are installed with the following: a) manufacturer's name and/or registered trademark, b) the number of Bangladesh standard and c) country of origin. Each product shall also be marked with the BSTI Certification Mark. The fixture should be placed in position with heavy type C.I. Brackets. 30 mm dia PVC waste water pipe with brass coupling (not exceeding 750 mm in length), basin waste with chain plug including making holes in walls and floors and fitting with wall, screws and mending good the damages, finishing etc. all complete approved and accepted by the Engineer-in-charge.				
			Over Counter: Approx. 560 X 475 mm size, minimum weight 10.0 kg	nos	2.00	4448.001	8,896.002

Signature

Signature

	Civil	10.20	Supply and installation of 0.47 mm thick zinc alum color coated profile sheet of durability class 2 with minimum warranty period of 10 years of durability, for roof, wall, capping, flashing, trimming, gutter etc. conforming to ASTM A792, Grade: 80, AZ150 gm/m ² , including the cost of necessary accessories (sheeting screws with washers, silicon sealant etc.), testing of materials etc. all complete as per drawing specification and direction of Engineer-in-charge (supplier has to produce papers to proof the source of material).	sqm	249.082	322.001	80,204.653
9	Civil	18.1.1	Supplying, fitting and fixing plain Particle board ceiling (Drop/Plain) (complying unit wt 499 to 550 kg/m ³ , bending strength 0.35 N/mm ² , max swelling 8%, moisture content not more than 10%), of 12 mm thick with best quality and well seasoned Garjan wood frame of section 50 mm x 38 mm at 600 mm x 600 mm in grid suspended from ceiling or roof or beam by 12 SWG double ply G.I. wire fixed to the ceiling by rowel plug, screws, hooks, nails etc, maintaining straight lines and desired finished level at bottom face including vertical strut as required, cutting holes in slabs or beams by electric drill machine and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, accessories, labour for installation, electricity charge, scaffolding, screws, nails, with best quality and approved colour etc. All complete, as per drawing design and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type).	sqm	44.015	2832.001	124,650.524
10	Civil	03.5.2	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II/B-M) Mass concrete in floor (1:2:4) with brick chips and local sand of F.M. 1.2.	cum	4.288	8,840.001	37,905.924
11	Civil	15.3	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to dado with cement (1:4) up to 150 mm including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	sqm	111.513	373.001	41,594.461

[Signature]

[Signature]

[Signature]

	Civil	26.31.7	Supplying, fitting and fixing of best quality pillar cock made from copper or copper alloy, chromium plated materials. The faucet conforms BDS EN 200:2009. The faucet tap shall be free from any leakage, permeation and other abnormalities. The water hammer value shall be 1.47 Mpa or under. The faucet after it has been operated 100000 times it shall be free from a seat-leakage and shall satisfy the reverse flow preventing performance. The inside and outside surfaces of the faucet shall be smooth and be free from blowholes, fissures, remarkable flows or injurious defects. The chromium plating on the faucet shall be of class 2 grade 1. The final coating should be done with chromium of minimum 0.1 micron. The faucet shall be made leak proof and fixing in position with selected tape etc. all complete approved and accepted by the Engineer-in-charge. CP One way Swan Cock	each	3.00	5920.001	17,760.003
13	Electrical	4.5.1.1	TPMCB Providing & fixing on a prepared board 500 volt grade following triple-pole molded case circuit breaker (TPMCCB) with thermal over-current and instantaneous electromagnetic short circuit release provision, Manufactured / Assembled and tested in accordance with IEC / VDE / NEMA / BS / JIS along with relevant BDS IEC standard.TPMCCBs accepted / approved by the Engineer-in-charge. 5 - 60 Amps.	each	2.00	4030.001	8,060.002
14	Electrical	M/r	Supply and fitting electric cable, switch, socket etc & repair of electric system	each	2.00	5000.001	10,000.002
15	Civil	Approved	Window glass & re-putting	each	25.00	200.00	5,000.025
						Total:	497,880.075
						Say	497,880.000

In word (Four lakh ninty seven thousand eight hundred eighty) taka only

Signature
৬৭/৭/২৬
রাজিয়া সুলতানা
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

Signature
৬৭/৭/২৬
মোঃ আরমান ভূইয়া
উপ-বিভাগীয় প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা।

Signature
৩১.০৭.২৩
মুজ্জা সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়াশা।