

Office of the Executive Engineer
Store Division, Dhaka WASA.

Name of the Work: Construction of Sewer Pit ,laying Sewer pipe & Cleaning Existing Sewer pit at Store division Compound,Dhaka WASA.


Sl. No.	Rate schedule item No.	Description of Item	Quantity	Unit.	Rate (Tk)	Amount (Tk)
1	2	3	4	5	6	7
1	26.83	Construction of masonry inspection pits up to a depth of 700 mm with 250 mm thick brick work in cement mortar (1:4) including 100 mm thick R.C.C. top slab (1:2:4) with 1% reinforcement, man-hole cover with locking arrangement including necessary earth work, side filling and one brick flat soling. 75 mm thick (1:3:6) base concrete for making invert channel and 12 mm thick (1:2) cement plaster with neat finishing etc. all complete approved and accepted by the Engineer- in- charge.				
	26.83.2	Clear 525 mm x 525 mm and depth 675 mm to 825 mm, average 750 mm for single 225 mm dia R.C.C. pipes and 400 mm PVC pipe with pit cover and 450 mm dia C.I. man-hole cover.	3 nos	each	7705.00	23115.00
2	26.45	Supplying and laying uPVC pipe for for underground including fitting, fixing etc. all complete approved and accepted by the Engineer- in- charge.				
	26.45.1	150 mm dia with wall thickness 4.5 mm - 6.6 mm uPVC pipe	25 m	P/m	913.00	22825.00
3	PWD-32.88	Clearing sldges & night soil from inspection pit	6.00 nos	Each	525.000	3150.000

Total Tk. 49090.00

In word TK. (Forty Nine Thousand Ninety) Only.


 Sub-Assistant Engineer
 Store Division
 Dhaka WASA


 Assistant Engineer
 Store Division
 Dhaka WASA


 Executive Engineer
 Store Division
 Dhaka WASA