

Office of the Executive Engineer
Store Division, Dhaka WASA.


Name of the Work: Rising of Surface drain east side of Godown No-4 at Store Division Compound. Dhaka WASA.

Sl. No.	Rate schedule item No.	Description of Item	Qty.	Unit	Rate (Tk)	Amount (Tk)
1	2	3	4	5	6	7
1	PWD-2022: 32.77	Labour charge for cleaning, washing, brooming from all heights and stacking of debris at a place beyond plinth area of the site during execution of repair works as per direction of the engineer-in-charge	2.50 Cum	P/cum	1451.001	3627.503
2	PWD-32.83	Cleaning, renewing of drain and apron with cement concrete or cement mortar etc as per direction of Engineer-in-charge.	15.50 m	P/m	232.001	3596.016
3	4.1	Brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:6) in foundation and plinth, filling the joints/interstices fully with mortar, racking out the joints, cleaning and soaking the bricks at least for 24 hours before use and curing at least for 7 days etc. all complete including cost of water, electricity and other charges and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M)	4.65 Cum	P/cum	7529.001	35009.855
4	PWD-15.3	Minimum 12 mm thick cement sand (F.M. 1:2) plaster with neat cement finishing to dado with cement (1:4) up to 150 mm including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	20.00 Sqm	P/Sqm	316.001	6320.020
5	L.S.	Site Cleaning as per direction of the Engineer in charge.	1.00 Item	P/Item	946.607	946.607

Total Tk. 49500.000

In word TK. (Forty Nine Thousand Five Hundred) Only.


 18/12/23
 Sub-Assistant Engineer
 Store Division
 Dhaka WASA


 18.12.23
 Assistant Engineer
 Store Division
 Dhaka WASA


 18/12/23
 Executive Engineer
 Store Division
 Dhaka WASA

Superintending Engineer
 SMWC Circle
 Dhaka WASA