

HOSSAIN BROTHERS & ENGINEERING WORKS

Price and Delivery Schedule for Goods (Form e-PG2-2A)

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Supply and installation of Sprinkler with RCC-Base Work: a. Sprinkler base: 18" high, 12" bottom & 6" top square shape base containing 2" inlet side to side and 1"/1.5" delivery line on top. Footing: for 2" pipe b. Sprinkler (composite materials & 30 feet diameter spray coverage range) for large scale Sprinkler (UPVC/ Polycarbonic material & 15 feet diameter spray coverage range) for medium scale c. SS Running pipe (6"X2) d. GI running pipe 1 feet (1") e. Socket 1" to 3/4" f. Socket 1" to 1" g. Ball Valve 1" to 1" Footing: for 2" pipe h. Running pipe 2 feet with both side thread cutting Socket 2"-	Set	72.000	Padma Water Treatment Plant	90	Bangladesh	25335.001	Twenty-Five Thousand Three Hundred and Thirty-Five point Zero Zero One	1824120.072	Eighteen Lakh Twenty-Four Thousand One Hundred and Twenty point Zero Seven Two

	in/out & 1? delivery."									
2	Supply of best quality standard size HDPE pipe 2" dia as per direction and approval of the engineer in charge.	m	500.000	Do	90	Bangladesh	520.001	Five Hundred and Twenty point Zero Zero One	260000.500	Two Lakh Sixty Thousand point Five
								Grand Total:	2084120.572	Twenty Lakh Eighty-Four Thousand One Hundred and Twenty point Five Seven Two

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md. Hossan on behalf of HOSSAIN BROTHERS & ENGINEERING WORKS

HOSSAIN BROTHERS & ENGINEERING WORKS

Price and Completion Schedule for Related Services (Form e- PG2-2B)

Price and Completion Schedule for Related Services

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Earth Work: a. 18" wide and 24" depth, channel excavation for pipeline installation. 1.2 ft X 2 ft X 800 ft= 2400 cft b. After every 30 feet there will be a connection box- excavation 24" X 24" for sprinkler base. 2 ft X 2 ft X 2 ft = 8 cft X 72 nos= 480 cft c. Channel excavation will be done in manual process through regular worker."	cft	2880.000	Padma Water Treatment Plant	90	Bangladesh	72.001	Seventy-Two point Zero Zero One	207362.880	Two Lakh Seven Thousand Three Hundred and Sixty-Two point Eight Eight
2	"Pipeline: a. Pipeline length 800 feet & 15% for footing wastage "	ft	800.000	Do	90	Bangladesh	65.001	Sixty-Five point Zero Zero One	52000.800	Fifty-Two Thousand point Eight
3	b. Bottom lining with 2" HDPE lining with SS footing (union) 5% for footing wastage.	ft	96.000	Do	90	Bangladesh	180.001	One Hundred and Eighty point Zero Zero One	17280.096	Seventeen Thousand Two Hundred and Eighty point Zero Nine Six
4	Drilling for connection from service water manhole and reconstruction of connection pit.	nos	4.000	Do	90	Bangladesh	15000.001	Fifteen Thousand point Zero Zero One	60000.004	Sixty Thousand point Zero Zero Four
5	Sprinkler Installation Charge.	nos	72.000	Do	90	Bangladesh	250.001	Two Hundred and Fifty	18000.072	Eighteen Thousand point Zero

								point Zero Zero One		Seven Two
6	Pressure Test: Pressure testing at minimum 6.5 bar and maximum 10 bar after completion of the work to ensure adequate pressure in the network all complete as per direction of the engineers in charge.	item	1.000	Do	90	Bangladesh	12000.001	Twelve Thousand point Zero Zero One	12000.001	Twelve Thousand point Zero Zero One
								Grand Total:	366643.853	Three Lakh Sixty-Six Thousand Six Hundred and Forty- Three point Eight Five Three

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md. Hossan on behalf of HOSSAIN BROTHERS & ENGINEERING WORKS