



ঢাকা পানি সরবরাহ ও পয়ঃ নিষ্কাশন কর্তৃপক্ষ, ঢাকা ওয়াসা

নির্বাহী প্রকৌশলীর কার্যালয়
সাভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট

Date: November 25, 2025

Measurement Book Report

Work Order No. : 46.113.626.00.00.054.2025. **Work Name** : Re-habilitation of deep tube-wells (DTW) 1-04 under SKWP.
WO-112
Work Order Date : 5/29/2025 **Tender No** :
Tender Amount : 998226 **Cost Center Name** : সাভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট
Contractor Name :

Details Expenses:

Particulars	Quantity	Unit	Rate	Amount
Mobilization for Re-habilitation	1	L/S	98500.001	98500.001
Cleaning of packed up well from reducer to bail-plug	133	p/m	820.001	109060.133
Chemical treatment and cleaning of well using Sodium I lexameta Phosphate/Sulfarmic acid.	13.3	Cum	4500.001	59850.013
Mechanical cleaning by water jetting using fresh water or by surge plunger i/e lowering & lifting of washing pipe	30	p/m	3745.001	112350.03
Disinfecting of the tube well	1	L/S	5000.001	5000.001
Supplying fitting fixing of 5" MS blind pipe.	84	p/m	3633.557	305218.788
Supplying sand for filling DTW, Cement casting & other relavent element.	1	Lot	129626.829	129626.829
Supplying fitting fixing and Installation of MS reducer over the existing 14"*5".	1	L/S	25208.001	25208.001

Particulars	Quantity	Unit	Rate	Amount
Supplying, fitting, fixing, and Installation of O ring.	5	p/m	5429.001	27145.005
Supply and installation of 200 mm dia best quality PVC Rubber Gasket.	20	Nos	129.558	2591.16
Cutting, Removal of Existing 150 mm uPVC pipe from bore hole & Related Others.	1	L/S	55000	55000
Bore hole camera program & Related Others. (Three times program is mandatory, if need more program Contractor will arrange).	1	Nos	55000	55000
Labor charge for site cleaning and removing the waste materials from the site complete as per direction of the Engineer-in charge.	1	L/S	6456.279	6456.279
Total				991,006.24

MD. Reazaul Karim
 নির্বাহী প্রকৌশলীর কার্যালয়
 সাভার-কেরানীগঞ্জ ওয়েলফিন্ড প্লান্ট