



ঢাকা পানি সরবরাহ ও পয়ঃ নিষ্কাশন কর্তৃপক্ষ, ঢাকা ওয়াসা

নির্বাহী প্রকৌশলীর কার্যালয়
সাভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট

Date: November 19, 2025

Measurement Book Report

Work Order No. : 46.113.626.00.00.028.24. **Work Name** : Re-generation of deep tube-wells (DTW) under IRP#1, SKWP
WO-81

Work Order Date : 4/10/2025 **Tender No** : 1060844
Tender Amount : 4463564 **Cost Center Name** : সাভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট

Contractor Name :

Details Expenses:

Particulars	Quantity	Unit	Rate	Amount
Cleaning of packedup well.	30	m	751.564	22546.92
Chemical treatment and cleaning of well.	39.6	Cum	4149.833	164333.387
Mechanical Cleaning from reducing cone to Bail Plug by high velocity hydraulic jetting	146.25	m	3651.486	534029.828
Development by Over Pumping: Carrying out step pumping	36	Hrs	8672.215	312199.74
Step Draw down and Discharge Test:	36	Hrs	6632.128	238756.608
Disinfecting the well.	3	L/S	4194.254	12582.762
Supply and installation 37mmdia best quality flexible pipe for LIT.	165	m	105.375	17386.875
Supply and installation of 200 mm dia best quality PVC Rubber Gasket.	54	Nos	295.353	15949.062
Mobilization for Re-generation work:	3	L/S	102577.757	307733.271
Lifting and Reinstallation of existing Sub-mersible pump before and after	3	Per Site	22627.217	67881.651

Particulars	Quantity	Unit	Rate	Amount
Re-generation work.				
Labor charge for site cleaning and removing the waste materials from the site.	2	L/S	8401.358	16802.716
Total				1,710,202.82

MD. Reazaul Karim
নির্বাহী প্রকৌশলীর কার্যালয়
সাভার-কেরানীগঞ্জ ওয়েলফিল্ড প্লান্ট