

M/S. Raihan Construction

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
499600.000	-5.000	474620.000	Four Lakh Seventy-Four Thousand Six Hundred And Twenty
	Grand Total:	474620.000	Four Lakh Seventy-Four Thousand Six Hundred And Twenty

This Tenderer's Quoted Price is Electronically Signed by Mr. Md. Raihan on behalf of M/S. Raihan Construction

M/S. Raihan Construction**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	Approved Rate	Dismantling of fan and inspection of blades, housing & shaft	Job	2.000	12400.000	Twelve Thousand Four Hundred	24800.000	Twenty-Four Thousand Eight Hundred	I have seen
2	N/A	Approved Rate	Cleaning of fan blades and housing with appropriate chemical	Job	2.000	12400.000	Twelve Thousand Four Hundred	24800.000	Twenty-Four Thousand Eight Hundred	I have seen
3	N/A	Approved Rate	Dynamic balancing check of fan rotor	job	2.000	18600.000	Eighteen Thousand Six Hundred	37200.000	Thirty-Seven Thousand Two Hundred	I have seen
4	N/A	Approved Rate	Lubrication of fan shaft bearing (grease SKF LGMT-3 or equivalent)	job	2.000	31000.000	Thirty-One Thousand	62000.000	Sixty-Two Thousand	I have seen
5	N/A	Approved Rate	Dismantling and internal inspection of 11 kW motor, Cleaning of motor windings (dry air blowing & vacuuming)	job	2.000	18600.000	Eighteen Thousand Six Hundred	37200.000	Thirty-Seven Thousand Two Hundred	I have seen
6	N/A	Approved Rate	Bearing condition check (sound & vibration check), Re-greasing of motor bearings (2310EK-C3)	pair	2.000	31000.000	Thirty-One Thousand	62000.000	Sixty-Two Thousand	I have seen
7	N/A	Approved Rate	Insulation resistance (IR) testing using megger, Shaft alignment check & coupling condition inspection	job	2.000	18600.000	Eighteen Thousand Six Hundred	37200.000	Thirty-Seven Thousand Two Hundred	I have seen
8	N/A	Approved Rate	Replacement of coupling rubber elements/bush	set	2.000	31000.000	Thirty-One Thousand	62000.000	Sixty-Two Thousand	I have seen
9	N/A	Approved Rate	Replacement of shaft sleeve H2310	no.	2.000	31000.000	Thirty-One Thousand	62000.000	Sixty-Two Thousand	I have seen
10	N/A	Approved Rate	Replacement of locating ring FRB 4/110	no.	2.000	31000.000	Thirty-One Thousand	62000.000	Sixty-Two Thousand	I have seen

11	N/A	Approved Rate	Reassembly of fan-motor set with proper alignment	no.	2.000	12400.000	Twelve Thousand Four Hundred	24800.000	Twenty-Four Thousand Eight Hundred	I have seen
12	N/A	Approved Rate	Temporary scaffolding, tools, rigging/lifting as required, Cleaning of work area and disposal of waste materials	job	2.000	1800.000	One Thousand Eight Hundred	3600.000	Three Thousand Six Hundred	I have seen
							Grand Total:	499600.000	Four Lakh Ninety-Nine Thousand Six Hundred	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Raihan on behalf of M/S. Raihan Construction