



Office of the Executive Engineer
Saidabad Water Treatment Plant Phase-2 (O&M)
Dhaka WASA

Subject:-Rust cleaning & painting of 7 nos. Treated water inlet outlet pipe, common header pipe, pump motor outer surface & butterfly valve

Bill of Quantities						
Sl. No.	Basis of rate	Description of item	Qty	Unit	Unit Rate (Tk.)	Total Amount (Tk.)
1	PWD SoR Civil Works Item No. 16.7.1	Epoxy enamel priming & painting including base, curing & thinner of nos. Treated water inlet outlet pipe, common header pipe, pump motor outer surface, butterfly valve & network pipe line of approve quality and color delivered from authorized local agent of the manufacturer in a sealed container, surface preparation including cleaning, drying, making free from dirt, grease, wax, removing chalked & scaled materisl, fungus (if required must be treated with fungicidal solution) flaking paints, washing the surface with soap water/caustic soda, mending good the surface defects, smoothing the surface by putty, sand papering the surface upto desired finishing, elapsing specified time for drying and recoating with necessary scaffolding all complete and accepted by engineer in charge.	1,070	Sq Meter	461.00	493,270.00
Total Amount including all Taxes, Tk=						493,270
Taka(In Words): Four Lac Ninety Three Thousand Two Hundred Seventy Only.						


28/12/25
এইচ এম নূর হক অপু
সিএমএমএস কো-অর্ডিনেটর
সাপাশো ফেজ-২ (ওএন্ডএম) বিভাগ
ঢাকা ওয়াসা।


28/12/25
মোঃ রাকিব হোসেন প্রধান
সহকারী প্রকৌশলী
সাপাশো ফেজ-২ (ওএন্ডএম) বিভাগ
ঢাকা ওয়াসা


28/12/25
সুজন চন্দ্র বর্মণ
নির্বাহী প্রকৌশলী
সাপাশো ফেজ-২ (ওএন্ডএম) বিভাগ
ঢাকা ওয়াসা


28/12/25
মোঃ এমরানুল ইসলাম
নির্বাহী প্রকৌশলী
সায়দাবাদ পানি শোধনাগার (পরিচালন)
ঢাকা ওয়াসা।