

Sikder Construction

Priced Bill of Quantities (BOQ)

The following 58 (Fifty Eight) Nos works Shall be Done by The Contractor who has Experience on Electrical Sub-Station Installation, Shifting, Repair and Maintenance works and Electric ABC License Holder. The bidder will complete the work within the least possible time. The Contractor will provide Free Service During Defect Liability Period of 12 (Twelve) Months of Concerning any Problem of this works. All Kind of Personal Protective Equipment (PPE) for the staffers will be provided by the bidder during this work.

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	N/A	Disconnection & Reconnection/Feeder Shut Down of H.T line by concerned DESCO/DPDC including all expenditures related to this works .	set	58.000	3335.001	Three Thousand Three Hundred And Thirty-Five Point Zero Zero One	193430.058	One Lakh Ninety-Three Thousand Four Hundred And Thirty Point Zero Five Eight	I have seen
2	N/A	N/A	Withdrawal & laying of existing NYSEFGbY HT cable with in 3 feet depth & 2 feet wide cable other related works as per direction the Engineer-in-charge. (14m x 58 Sites) = 812 m.	per meter	812.000	455.001	Four Hundred And Fifty-Five Point Zero Zero One	369460.812	Three Lakh Sixty-Nine Thousand Four Hundred And Sixty Point Eight One Two	I have seen
3	N/A	N/A	HT cable laying (lifting & downing) in presense of REB/DPDC's representative & install the cable in a secured place with supplying of necessary materials such as cable connector, GI wire, creampit etc. to complete as per direction of the Engineer-in-charge.	item	58.000	4000.001	Four Thousand Point Zero Zero One	232000.058	Two Lakh Thirty-Two Thousand Point Zero Five Eight	I have seen
4	N/A	N/A	Fitting and fixing of departmentally supplied 3x50 rm heat shrink termination kit at transformer and HT cable side.	per-kit	58.000	5200.001	Five Thousand Two Hundred Point Zero Zero One	301600.058	Three Lakh One Thousand Six Hundred Point Zero Five Eight	I have seen
5	N/A	N/A	Installing of DOFC supplied from division as per direction of the Engineer in charge.	p/set	50.000	2000.001	Two Thousand Point Zero Zero One	100000.050	One Lakh Point Zero Five	I have seen

6	N/A	N/A	Cleaning and servicing of X-former HT/LT bush as well as new cable connection to complete as per direction of the Engineer-in-charge.	item	58.000	525.001	Five Hundred And Twenty-Five Point Zero Zero One	30450.058	Thirty Thousand Four Hundred And Fifty Point Zero Five Eight	I have seen
7	N/A	N/A	Insulation megger testing of Transformer, LT-HT cable, sub pump motor, pump cable, VFD etc. as per direction of the Engineer-in-charge.	per-item	50.000	2800.001	Two Thousand Eight Hundred Point Zero Zero One	140000.050	One Lakh Forty Thousand Point Zero Five	I have seen
8	N/A	N/A	Repairing & maintenance of existing transformer fencing with welding, jointing & painting by contractor supplied paint-thinner etc.	Each	30.000	4400.001	Four Thousand Four Hundred Point Zero Zero One	132000.030	One Lakh Thirty-Two Thousand Point Zero Three	I have seen
							Grand Total:	1498941.174	Fourteen Lakh Ninety-Eight Thousand Nine Hundred And Forty-One Point One Seven Four	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Kamal Sikder on behalf of Sikder Construction