


**Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.**


ESTIMATE


Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front Of House # 37, Road # 12, Baridhara K Block (DMA-810) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	75 mm dia HDPE Pipe	6.00	P/M			Supply by Sub store
2	Approved Rate	110 mm dia HDPE Pipe	5.00	P/M			Supply by Sub store
3	Approved Rate	110 mm dia HDPE Sleeve E.F	2.00	Nos			Supply by Sub store
4	Approved Rate	75 mm dia HDPE Sleeve E.F	2.00	Nos			Supply by Sub store
7	Approved Rate	Excavation and removal of soil from the trench bottom beyond allowable depth in accordance with the technical specification and direction of Engineering in charge,	35.92	Cum	331.000	11889.520	
8	Approved Rate	supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	34.60	Cum	578.000	19998.800	
9	Approved Rate	One layer brick flat soling in foundation with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling etc.	16.45	p/sqm	636.001	10462.216	
10	Approved Rate	Skilled Technician	2.00	P/Person	1000.00	2,000.00	
11	Approved Rate	Labour Charge	7.000	P/Person	800.000	5600.000	
Total=						49950.536	

In words: Forty Nine Thousand Nine Hundred Fifty point Five Three Six TK Only


২২/০২/১৬
আব্দুল হোসেন
উপ-সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াশা।


২২/০২/১৬
ভূষার চন্দ্র বর্মেন
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াশা।


২২/০২/১৬
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াশা।