

M/S. METRO INTERNATIONAL CORPORATION**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	civil	21.8	Supplying, fitting and fixing 12 BWG barbed wire (2 ply, 4 points) in fencing work @ 150 mm c/c both horizontally and vertically, supported by 38 mm x 38 mm x 6 mm M.S. Y-shape angle post (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) 600 mm vertical and 450 mm inclined or as per requirement @ 2.4 m c/c including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supplying all necessary materials complete in all respect and accepted by the Engineer-in-charge. (Rate is excluding the cost of paint, R.C.C /brick work or C.C. which is to be paid as per corresponding items in the schedule).	sqm	61.338	1034.001	One Thousand And Thirty-Four Point Zero Zero One	63423.553	Sixty-Three Thousand Four Hundred And Twenty-Three Point Five Five Three	I have seen

2	civil	10.21	Supply and installation of 0.457 mm thick corrugated galvanized iron sheet (Bangladesh made) having min weight 63-65 kg per bundle (2'-6" width, 70 ? 72 rft long) fitted and fixed on M.S. sections with 'J' hook or wooden purlin with screws, limpet washers and putty etc. (up to level-4) all complete and accepted by the Engineer-in-charge.	sqm	69.294	578.001	Five Hundred And Seventy-Eight Point Zero Zero One	40052.001	Forty Thousand And Fifty-Two Point Zero Zero One	I have seen
3	civil	18.2.1.2	"Supplying, fitting and fixing 12 mm thick Burma teak (BT) veneered board/ ply board/ particle board in walling with best quality and well seasoned garjan wood frame of section of 50 mm x 25 mm at 600 mm x 600 mm in grid, including groove where necessary, fitted and fixed to wall by plugs, nails, screws etc. maintaining leveled and finished exposed faces including making holes in wall and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, electricity, accessories, labour for installation, scaffolding, screws, nails etc. All complete as per design, approved sample and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type). "	sqm	31.227	3098.001	Three Thousand And Ninety-Eight Point Zero Zero One	96741.277	Ninety-Six Thousand Seven Hundred And Forty-One Point Two Seven Seven	I have seen
4	civil	4.15	125 mm brick work with first class bricks with cement sand (F.M. 1:2) mortar (1:6) and making	sqm	50.186	1160.001	One Thousand One Hundred	58215.810	Fifty-Eight Thousand Two Hundred	I have seen

			bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/ B-M) In ground floor				And Sixty Point Zero Zero One		And Fifteen Point Eight One	
5	civil	15.1.1	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity.	sqm	401.859	315.001	Three Hundred And Fifteen Point Zero Zero One	126585.986	One Lakh Twenty-Six Thousand Five Hundred And Eighty-Five Point Nine Eight Six	I have seen
6	civil	16.11	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease.	sqm	527.881	213.001	Two Hundred And Thirteen Point Zero Zero One	112439.180	One Lakh Twelve Thousand Four Hundred And Thirty-Nine Point One Eight	I have seen
							Grand Total:	497457.807	Four Lakh Ninety-Seven Thousand Four Hundred And Fifty-Seven Point Eight Zero Seven	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. MD TAHER on behalf of M/S. METRO INTERNATIONAL CORPORATION