

Pinion Powertech**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	A	N/A	Carrying the pump set including other materials ? column pipes, shaft, bend, motor discharge head, clamp, tools etc. complete from central store/F.M Divn. to P/S and returning of the rest by providing vehicles , drivers, fuell all complete.	Per trip	50.000	2025.001	Two Thousand And Twenty-Five Point Zero Zero One	101250.050	One Lakh One Thousand Two Hundred And Fifty Point Zero Five	I have seen
2	A	N/A	Providing Tripod & chain pulley including carrying, setting, dismantling and returning all complete.	Per set	50.000	1793.001	One Thousand Seven Hundred And Ninety-Three Point Zero Zero One	89650.050	Eighty-Nine Thousand Six Hundred And Fifty Point Zero Five	I have seen
3	A	N/A	Withdrawal of submersible pump, cable, bend etc. all complete	Per set	50.000	978.001	Nine Hundred And Seventy-Eight Point Zero Zero One	48900.050	Forty-Eight Thousand Nine Hundred Point Zero Five	I have seen
4	A	N/A	Withdrawn of flange ended column pipe (37 nos per well on average Total=50x37=1850 Nos), pump cable, cable guard, bend, rubber gasket, base plate etc.	Each	1850.000	247.001	Two Hundred And Forty-Seven Point Zero Zero One	456951.850	Four Lakh Fifty-Six Thousand Nine Hundred And Fifty-One Point Eight Five	I have seen
5	A	N/A	Collecting of DTW data such as static water level (SWL), total fixture length clear, continuity test of sub-pump cable & motor.	per job	50.000	350.001	Three Hundred And Fifty Point Zero Zero One	17500.050	Seventeen Thousand Five Hundred Point Zero Five	I have seen
6	A	N/A	Installation of sub-pump, motor, cable, bend etc. all complete	Per set	50.000	943.001	Nine Hundred And Forty-Three	47150.050	Forty-Seven Thousand One Hundred	I have seen

							Point Zero Zero One		And Fifty Point Zero Five	
7	A	N/A	Installaion of flange ended column pipe (38 nos per well on average Total=38x50=1900 Nos), pump cable, cable guard, bend, rubber gasket, base plate etc.	Each	1900.000	268.001	Two Hundred And Sixty-Eight Point Zero Zero One	509201.900	Five Lakh Nine Thousand Two Hundred And One Point Nine	I have seen
8	A	N/A	Site preparation work to ensure the proper working environment such as sand filling for MS Tripod setting etc.	per job	16.000	2000.001	Two Thousand Point Zero Zero One	32000.016	Thirty-Two Thousand Point Zero One Six	I have seen
9	A	N/A	Disconnection, reconnection, cleaning of stater/VFD & all other electrical connections, setting and adjusting all electrical parameter according to new install pump motor set and temperature controller under supervision of a ABC licence holder supervisor by skilled electrician.	per job	50.000	1874.001	One Thousand Eight Hundred And Seventy-Four Point Zero Zero One	93700.050	Ninety-Three Thousand Seven Hundred Point Zero Five	I have seen
							Grand Total:	1396304.066	Thirteen Lakh Ninety-Six Thousand Three Hundred And Four Point Zero Six Six	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. MD. KAWSAR on behalf of Pinion Powertech

Pinion Powertech**Tenderer's Quoted Price**

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
1396304.060	-5.000	1326488.857	Thirteen Lakh Twenty-Six Thousand Four Hundred And Eighty-Eight Point Eight Five Seven
	Grand Total:	1326488.857	Thirteen Lakh Twenty-Six Thousand Four Hundred And Eighty-Eight Point Eight Five Seven

This Tenderer's Quoted Price is Electronically Signed by Mr. MD. KAWSAR on behalf of Pinion Powertech