

AYAT ENTERPRISE

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item no.	Group	Item Code (if any)	Description of Item	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	Select 'YES' to see the Grand Total
1	Civil	-	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the Engineer.	Cum	40.289	1080.001	One Thousand And Eighty Point Zero One	43512.160	Forty-Three Thousand Five Hundred And Twelve Point One Six	Yes
2	Civil	-	"Dismantling of R.C.C. in roof slab and removal of debris to a safe distance." a) Brick	P/Sqm	1.250	62.001	Sixty-Two Point Zero One	77.501	Seventy-Seven Point Five Zero One	Yes
3	Civil	-	b) C.C/R.C.C	Cum	1.900	3319.001	Three Thousand Three Hundred And Nineteen Point Zero One	6306.101	Six Thousand Three Hundred And Six Point One Zero One	Yes
4	Civil	-	Lean/ blinding concrete (1:3:6) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) Lean/ blinding concrete in floor (1:3:6) with cement, brick chips and sand of F.M. 1.2	Cum	1.035	9259.001	Nine Thousand Two Hundred And Fifty-Nine Point Zero One	9583.066	Nine Thousand Five Hundred And Eighty-Three Point Zero Six Six	Yes
5	Civil	-	Supplying, fitting and fixing 12 BWG barbed wire fencing in a circular shape of 600 mm dia and 100 mm pitch fitted with MS rod casing (made by 8 nos. 10 mm dia plain bar in a circular pattern and placed at equal interval), 38 x 38 x 6 mm M.S. angle post (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) and 600 mm vertical and 450 mm inclined placed @ 3.0 m c/c including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supply of all necessary materials complete in all respect and accepted by the Engineer-in-charge. (Rate is excluding the cost of Painting).	P/M	19.811	2553.001	Two Thousand Five Hundred And Fifty-Three Point Zero One	50577.502	Fifty Thousand Five Hundred And Seventy-Seven Point Five Zero Two	Yes
6	Civil	-	Centering and shuttering, including strutting, propping etc. (The formwork must be rigid enough both in and out of plane, to make the concrete surface true to the designed shape and size by using necessary MS sheets of minimum 16 BWG, angles of minimum size 40 mm x 40 mm x 5 mm, flat bars etc.) and removal of form for : Individual and combined footing	P/Sqm	64.740	582.001	Five Hundred And Eighty-Two Point Zero One	37678.744	Thirty-Seven Thousand Six Hundred And Seventy-Eight Point Seven Four Four	Yes
7	Civil	-	125 mm brick works with first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making	P/Sqm	72.454	1408.001	One Thousand	102015.304	One Lakh Two	Yes

			bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M)				Four Hundred And Eight Point Zero Zero One	Thousand And Fifteen Point Three Zero Four		
8	Civil	-	Minimum 12 mm thick cement sand Plaster (1:4) to dado and plinth wall up to 150 mm blow ground level and floor with neat cement finishing in/c finishing the edges and corner and curing at last for 7 days etc all complete.	P/Sqm	343.884	392.001	Three Hundred And Ninety-Two Point Zero Zero One	134802.871	One Lakh Thirty-Four Thousand Eight Hundred And Two Point Eight Seven One	Yes
9	Civil	-	Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. up to desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	P/Sqm	343.884	274.001	Two Hundred And Seventy-Four Point Zero Zero One	94224.559	Ninety-Four Thousand Two Hundred And Twenty-Four Point Five Five Nine	Yes
10	Civil	-	Premium synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in two coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	P/Sqm	13.285	235.001	Two Hundred And Thirty-Five Point Zero Zero One	3121.988	Three Thousand One Hundred And Twenty-One Point Nine Eight Eight	Yes
11	Civil	-	Site Cleaning	L/S	2.000	5000.001	Five Thousand Point Zero Zero One	10000.002	Ten Thousand Point Zero Zero Two	Yes
							Grand Total:	491899.798	Four Lakh Ninety-One Thousand Eight Hundred And Ninety-Nine Point Seven Nine Eight	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. FERDUS HOSEN on behalf of AYAT ENTERPRISE