



স্মারক নং: M/S D.T.S Consolidators-01

Date: 12/03/2026

Tracking No :2026033121549897228

বরাবর,
নির্বাহী প্রকৌশলী
মডস জোন-৪
ঢাকা ওয়াসা।

বিষয়ঃ Repair & Maintenance of pump house, Chlorine room and necessary renovation works of Agargoan-4 & Agargoan-6 water pump compound under MODS Zone-4, Dhaka WASA কাজের সমাপ্তির বিল পরিশোধ প্রসঙ্গে।

Contract No : 46.113.408.00.00.066.25/e-T-H-40-NOA/CA
Work Order No : 46.113.408.00.00.066.25-051

Date : 28/01/2026
Date : 28/01/2026

উপর্যুক্ত বিষয় ও সূত্রের প্রেক্ষিতে জানানো যাচ্ছে যে, Repair & Maintenance of pump house, Chlorine room and necessary renovation works of Agargoan-4 & Agargoan-6 water pump compound under MODS Zone-4, Dhaka WASA কাজটি দায়িত্ব প্রাপ্ত প্রকৌশলীগণের নির্দেশনা অনুযায়ী সুষ্ঠুভাবে গত 12/03/2026 ইং তারিখে 100% সম্পন্ন করেছি।

এমতাবস্থায়, উক্ত কাজের অনুকূলে পেমেন্ট ইনভয়েজ গ্রহণ করতঃ TK 4,70,642.000/- (Four Lakhs Seventy Thousand Six Hundred Forty-Two Taka Only) প্রদানের প্রয়োজনীয় ব্যবস্থা গ্রহণের জন্য অনুরোধ করছি।

নিবেদক,

M. Rahman.

31/03/2026 12:00:35 PM
Mahbubur Rahman
Authority
M/S D.T.S CONSOLIDATORS



Bill Application Information

Name of Cost Center:	MODS Zone-4
Name of Work:	Repair & Maintenance of pump house, Chlorine room and necessary renovation works of Agargoan-4 & Agargoan-6 water pump compound under MODS Zone-4, Dhaka WASA
Tender ID :	1186470
Tender Method :	LTM EGP
Name of Firm :	M/S D.T.S CONSOLIDATORS
Contract No :	46.113.408.00.00.066.25/e-T-H-40-NOA/CA
Work Order No :	46.113.408.00.00.066.25-051
Contract Date :	28/01/2026
Work Order Date :	28/01/2026
Work End Date:	13/03/2026
Estimate Completion Date:	12/03/2026
Work Status :	100%
Mode of Bill :	
Bill Amount :	4,70,642.000
Cost Center Head Name :	MD. EMDADUL HAQUE



M/S D.T.S CONSOLIDATORS

G-10, Eastern Housing Project, South Banasree, Khilgaon, Dhaka-1219

Email: shararrahman834@gmail.com

Phone No: 01819281932

Invoice No : M/S D.T.S Consolidators-01

Date: 12/03/2026

Payment Invoice

SL	Description	Quantity	Unit	Rate	Total
1	Site development/Improvement by carted earth or dredged sand, sandy silt (free from any organic, foreign, environmental hazardous substances) carried by head or truck or any other means including cost of cutting or by dredging of sand, sandy silt, all; including local carrying, placing the earth/sand, sandy silt in the designated area, maintaining slopes, breaking lumps, levelling and dressing in layers up to finished level etc. all complete as per direction and accepted by the engineer in charge.	32.46	Cum	481.00	15,613.260
2	25 mm thick artificial patent stone (1:2:4) flooring with cement, best quality coarse sand (50% quantity of Sylhet sand or coarse sand of equivalent F.M. 2.2 and 50% best quality local sand of FM 1.2) and 12 mm down well graded brick chips including breaking chips, screening, laying the concrete in alternate panels, compacting and finishing the top s with neat cement and curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) In ground floor	31.41	Sqm	566.00	17,778.060
3	Stripping of unserviceable plaster including racking out joints, cleaning etc.	206.32	Sqm	31.00	6,395.920
4	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to plinth wall with cement (1:4) up to 150 mm below ground level including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	206.32	Sqm	316.00	65,197.120
5	Brick works with first class bricks with cement sand (F.M. 1.2) mortar (1:6) in foundation and plinth, filling the joints/interstices fully with mortar, racking out the joints, cleaning and soaking the bricks at least for 24 hours before use and curing at least for 7 days etc. all complete including cost of water, electricity and other charges and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M)	1.51	Cum	7,529.00	11,368.790
6	Renewing of Exterior premium acrylic emulsion paint of approved brand and quality	352	Sqm	177.00	62,304.000
7	CEILING FAN Supplying & fixin-e AC capacitor rype ceiling fan (without regulator) of. following specifications and sizes complete wirh riri_r.oi"r.ir Inf long and 0.75-t.0, dia, 2.3 mm rhickness fVS pipe Oo*n/oi. i"r"r.A cast aluminum blades. 2.5 pf 400V AC .upu.i.or,.mopy i"luf."for,, bearing, best quality silicon sheet.core. besl qualiry copper made super enamel wire, aluminum alloyed casting body/metal i"al, i""irs, rfd pl, P E 21.1 ::1:d.1..id h!"ar docu parnr as required as per BDS 8t8 erc connecting PVC uire complete as required. Rated voltage: 2_10 volts	2	Each	3,914.00	7,828.000
8	Renewing of standard synthetic enamel paint to door-windows frame and shutter: 2 coat	92	Sqm	183.00	16,836.000
9	Supplying, fitting and fixing steel grill fencing of any	27.45	Sqm	5,254.00	144,222.300

SL	Description	Quantity	Unit	Rate	Total
	design and shape made with 19 mm x 6 mm box tube (box made with 2 nos. 19 mm x 19 mm x 6 mm angle by continuous welding) placed vertically @ 150 mm c/c and welding the said vertical boxes with two Nos. horizontal 25 x 25 x 6 mm angle box (made with 2 Nos. 25 x 25 x 6 mm angle by welding), placing one at bottom and another at top and again fitting & fixing by welding the said horizontal tube box (with vertical 38 mm x 38 mm x 6 mm angle box post made with 2 nos. 38 mm x 38 mm x 6 mm angle by welding) provided @ 1800 mm c/c including embedding the tube box post in brick R.C.C. pillar or core wall up to 375 mm depth after cutting grooves in wall/pillar including mending good the damages with C.C. (1:2:4) and finishing, curing, 2 coats of approved synthetic enamel paint over a coat of anti-corrosive paint etc. all complete as per design, drawing and accepted by the Engineer-in-charge. (Rate is excluding the				
10	Supplying, fitting, fixing, and installation of ordinary type M.S. gate (double leaf) of any design and shape with 38 x 38 x 6 mm M.S. Angle outer frame having 16 mm dia M.S. rod placed vertically @ 75 mm c/c. at bottom part and top part (200 mm long arrows) and also placed horizontally at bottom for interconnection of 16 mm dia M.S. rod placed vertically as per design, the top part covered with 18 BWG M.S. sheet and fixed with 4 nos. 38 mm x 6 mm F.I. bars placed diagonally and 4 Nos. 38 mm x 6 mm F.I. bars placed horizontally and vertically all passing through the center, providing locking arrangements on 3 mm thick M.S. plate one for main gate and one for minimum 600 mm x 1025 mm pocket gate with 38 mm x 38 mm x 6 mm M.S. angle and 16 mm dia M.S. rod placed vertically @ 75 mm c/c, providing 38 mm x 38 mm x 6 mm M.S. angle clamps fitted and fixed with the outer frame of the main gate, the clamp being embedded in R.C.C. or R. C.C. core pillar with cement concrete (1:2:4) in masonry including cutting holes and mending good the damages, finishing, curing etc. including riveting, welding as and where necessary, painting two coats with approved quality of synthetic enamel paint over a coat of priming of anti-corrosive paint etc. all complete as per drawing, design and accepted by the Engineer-in-charge(Rate is excluding the cost of paint).	15.61	Sqm	6,667.00	104,071.870
11	Cleaning, washing, brooming and taking away of debris from the site during and or after the completion of the repair works in all heights by truck or by any other means as per direction of the engineer-in-charge	12.76	Cum	808.00	10,310.080
12	light /exhaust or wall bracket lan point/F an point	4	point	1,203.00	4,812.000
13	Renewing of Interior standard acrylic emulsion paint (Plastic) to walls and ceiling: 2 coat	185	Sqm	155.00	28,675.000
Total:					4,70,642.000
Deduction 5 % less:					24,770.620
Ground Total (Actual):					4,70,641.780
Ground Total(Round):					4,70,642.000

In Words: Four Lakhs Seventy Thousand Six Hundred Forty-Two Taka Only.

Sincerely,

M. Rahman



M/S D.T.S CONSOLIDATORS
G-10, Eastern Housing Project, South Banasree, Khilgaon, Dhaka-1219
Email: shararrahan834@gmail.com
Phone No: 01819281932

Bangladesh Electronic Fund Transfer Network (BEFTN)

Purpose Of Pay	Bank Name	Branch Name	Routing No	Account No	Type	Amount	Receiver Name	Mobile No
	NRB COMMERCIAL BANK LTD.	PRINCIPAL	260275354	010133300 003967	Current (CD) Account		M/S D.T.S CONSOLIDATORS	01819281932

Sincerely,

M. Rahman

31/03/2026 12:00:35 PM
Mahbubur Rahman
Authority
M/S D.T.S CONSOLIDATORS