

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer

Civil Maintenance Division

Dhaka WASA, Dhaka

6th floor, WASA Bhaban

98 Kazi Nazrul Islam avenue, Dhaka.

Name of the Work: Replacement of existing soil, waste and ventilation pipe of Asadgate officers quarter and ancillary maintenance work of babor road staff quarter, Dhaka WASA.

Sl. No.	Item No.	Description of the item	Quantity	Unit	Rate	Amount
1	PWD-22 26.43	Supplying different inside dia best quality uPVC soil, waste and ventilation pipe having specific gravity 1.35 - 1.45, wall thickness 2.5 mm - 3.0 mm, and other physical, chemical, thermal, fire resistivity properties etc. as per BSTI approved manufacturer standards or ASTM, BS/ISO/IS standards fitting and fixing in position with sockets, bends, of uPVC Pipe with all accessories such as Round grating /domed roof grating bands, sockets etc. approved and accepted by the Engineer- in- charge.				
	26.43.2	100 mm inside dia wall thickness 3.4- 4.0 mm	25.000	meter	881.000	22025.000
2	PWD-22 26.46	Supplying different inside dia best quality CPVC pressure pipe for water supply having specific gravity 1.35 - 1.45, and other physical, chemical, thermal, fire resistivity properties etc. as per BSTI approved manufacturer standards or ASTM, BS/ISO/IS standards fitting and fixing in position with sockets, bends, with all accessories such as round grating/domed roof grating, bends, sockets etc. approved and accepted by the Engineer-in-charge.				
	26.46.3	25 mm dia wall thickness 3.4 mm - 4.0 mm	25.000	meter	453.000	11325.000
3	PWD-22 3.5	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II/B-M)				
	3.5.1	Mass concrete in foundation (1:2:4) with brick chips and local sand of F.M. 1.2.	1.800	cum	8885.000	15993.000
Total=						49343.000
Sy total=						49343.000

In Word: Taka Forty nine thousand three hundred forty three Only.

H.R.

০৭.০৭

২০২৪

মাসুদ রিয়াজুল ইসলাম
উপ সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াশা

০৭.০৭.২৪

মুজিব সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়াশা