

**Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.**


Estimate

Name of Works: Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front Of Mannat House, Sulmaid Purbopara, Bosumoti Road (DMA-803) under MODS Zone-8, Dhaka

SL. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	7.00	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Sleeve E.F	2	Nos	5000.00	10,000.00	
3	Approved Rate	Earth work: (3.67*7.5*1.52)= 41.84 cum	41.84	Cum	149.00	6233.86	
4	Approved Rate	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe (3.67*7.5*1.52)= 41.84 cum	41.84	Cum	503.00	21045.52	
5	Approved Rate	Mechanics Charge	2	P/Person	1000.00	2000.00	
6	Approved Rate	Daily Labour	8	P/Person	800.00	6400.00	
7	Approved Rate	Hire charge of de-watering pump	2	P/Day	2000.00	4000.00	
Total (Tk.)=						49679.38	
Say Total (Tk.)=						49679/-	

In words: Forty Nine Thousand Six Hundred and Seventy Nine Taka Only.


আব্দুল হেলিম
উপ-সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।


মোঃ গোলাম মোস্তফা খন্দকার
উপ-বিভাগীয় প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াসা।


অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।