

M.M. Engineering Enterprise**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	N/A	Generator Canopy & Chassis repairing, Denting, Rubbing and Rust Removing etc as required as per direction of EIC.	Job	8.000	6000.001	Six Thousand point Zero Zero One	48000.008	Forty-Eight Thousand point Zero Zero Eight	I have seen
2	N/A	N/A	Chemical wash with Tarpin the surroundings of the generator should be cleaned as per Direction of the Engineer in Charge.	Liter	52.000	260.001	Two Hundred and Sixty point Zero Zero One	13520.052	Thirteen Thousand Five Hundred and Twenty point Zero Five Two	I have seen
3	N/A	N/A	The rusted areas of the generator canopy shall be cleaned with series paper and necessary puttying and fitting-fixing shall be done as directed by the Engineer-in-Charge.	Kg	85.000	500.001	Five Hundred point Zero Zero One	42500.085	Forty-Two Thousand Five Hundred point Zero Eight Five	I have seen
4	N/A	N/A	External painting of generator shall be done initially by powder spray as directed by Engineer-in-Charge.	Pound	90.000	500.001	Five Hundred point Zero Zero One	45000.090	Forty-Five Thousand point Zero Nine	I have seen
5	N/A	N/A	Docu Paint (Heat proof) Painting with Engine body and Alternator canopy and others as per Direction of the Engineer in Charge.	Pound	100.000	900.001	Nine Hundred point Zero Zero One	90000.100	Ninety Thousand point One	I have seen
6	N/A	N/A	Repairing, Denting, Rubbing and removing rust from Lub oil tank & Fuel tank and Providing fitting-fixing of SS Sheet thickness of 3mm, 5sgft (approximate) or net with frame (same size approximate) at canopy, Chassis or base of generator (if necessary) as per Direction of the Engineer in Charge.	Job	8.000	6000.001	Six Thousand point Zero Zero One	48000.008	Forty-Eight Thousand point Zero Zero Eight	I have seen
7	N/A	N/A	Welding machine rent, Welder, Expert Labour, Service Charge and Generator serial Numbering work, providing	Job	8.000	10000.001	Ten Thousand point Zero Zero One	80000.008	Eighty Thousand point Zero Zero Eight	I have seen

			fitting-fixing of heet proof foam/glasswool insulator with soundproofing inside the canopy to ensure effective noise reduction as per Direction of the Engineer in Charge.							
8	N/A	N/A	SPMCB 16A 6-10k.	Each	4.000	526.001	Five Hundred and Twenty-Six point Zero Zero One	2104.004	Two Thousand One Hundred and Four point Zero Zero Four	I have seen
9	N/A	N/A	Site cleaning work for removing all debris from the site with contractor own all complete as per Direction of the Engineer in Charge.	Job	8.000	2000.001	Two Thousand point Zero Zero One	16000.008	Sixteen Thousand point Zero Zero Eight	I have seen
10	N/A	N/A	Fuel Tank Cape.	Each	4.000	750.001	Seven Hundred and Fifty point Zero Zero One	3000.004	Three Thousand point Zero Zero Four	I have seen
11	N/A	N/A	5 Amps 110v-220v emergency stop push button switch.	Each	4.000	750.001	Seven Hundred and Fifty point Zero Zero One	3000.004	Three Thousand point Zero Zero Four	I have seen
12	N/A	N/A	Radiator Cap for Generator.	Each	4.000	500.001	Five Hundred point Zero Zero One	2000.004	Two Thousand point Zero Zero Four	I have seen
13	N/A	N/A	Battery cable (30 RM DC Cable).	Feet	12.000	450.001	Four Hundred and Fifty point Zero Zero One	5400.012	Five Thousand Four Hundred point Zero One Two	I have seen
							Grand Total:	398524.387	Three Lakh Ninety-Eight Thousand Five Hundred and Twenty-Four point Three Eight Seven	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Mohammad Hossain on behalf of M.M. Engineering Enterprise