

M/S. N. ISLAM & CO**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	N/A	Earth work in excavation in all kinds of soil for foundation trenches including layout, providing center lines, local bench-mark pillars, levelling, ramming and preparing the base, fixing bamboo spikes and marking layout with chalk powder, providing necessary tools and plants, protecting and maintaining the trench dry etc., stacking, cleaning the excavated earth at a safe distance out of the area enclosed by the layout etc. all complete and accepted by the Engineer-in-charge, subject to submit method statement of carrying out excavation work to the Engineer-in-charge for approval. However, engineer's approval shall not relieve the contractor of his responsibilities and obligations under the contract. Layout and marking for earthwork in excavation in foundation accepted by the Engineer-in-charge. [Plinth area of the structure shall be considered for measurement].	cum	112.147	189.001	One Hundred and Eighty-Nine point Zero Zero One	21195.895	Twenty-One Thousand One Hundred and Ninety-Five point Eight Nine Five	I have seen
2	N/A	N/A	Sand filling in foundation trenches and plinth with sand having min. F.M. 1.2 in 150 mm in layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	cum	25.807	1296.001	One Thousand Two Hundred and Ninety-Six point Zero Zero One	33445.898	Thirty-Three Thousand Four Hundred and Forty-Five point Eight Nine Eight	I have seen
3	N/A	N/A	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks including preparation of bed	sqm	193.211	553.001	Five Hundred and Fifty-Three	106845.876	One Lakh Six Thousand Eight	I have seen

			and filling the interstices with local sand, leveling etc. complete and accepted by the Engineer-in-charge.				point Zero Zero One		Hundred and Forty-Five point Eight Seven Six	
4	N/A	N/A	Brick Works Foundation : Brick works with 1st class bricks in cement mortar (1:4) in exterior walls including filling the interstices fully with mortar, raking out the joints, cleaning and soaking the bricks at least for 24 hours before use and necessary scaffolding, curing at least 7 days etc. All complete as per direction of Engineer-in-charge.	cum	13.896	6769.001	Six Thousand Seven Hundred and Sixty-Nine point Zero Zero One	94062.038	Ninety-Four Thousand AND Sixty-Two point Zero Three Eight	I have seen
5	N/A	N/A	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II/A-M). Mass concrete in foundation (1:2:4) with brick chips and local sand of F.M. 1.2.	cum	16.355	8886.001	Eight Thousand Eight Hundred and Eighty-Six point Zero Zero One	145330.546	One Lakh Forty-Five Thousand Three Hundred and Thirty point Five Four Six	I have seen
6	N/A	N/A	Supplying and laying of single layer polythene sheet weighing one kilogram per 6.5 square meter in floor or any where below cement concrete complete in all respect and accepted by Engineer-in-charge.	sqm	214.678	47.001	Forty-Seven point Zero Zero One	10090.081	Ten Thousand AND Ninety point Zero Eight One	I have seen
7	N/A	N/A	Mild steel (Angle) and pipe Grade 250 with minimum fy = 250 MPa, work in roof truss: supplying and fabrication of mild steel sections as per design, hoisting, fitting and fixing in position with bolt and nuts or rivets or welds and providing two coats of anti-corrosive paint over a prime coat of red oxide paint etc. complete and accepted by the Engineer-in-charge. (Measurement to be given for truss member only).	kg	2324.175	162.499	One Hundred and Sixty-Two point Four Nine Nine	377676.113	Three Lakh Seventy-Seven Thousand Six Hundred and Seventy-Six point One One Three	I have seen
8	N/A	N/A	Supply and installation of 0.47 mm thick zinc alum color coated profile sheet for roof, wall, capping, flashing, trimming, gutter etc. conforming to ASTM A792, Grade: 80, AZ150 gm/m2, including the cost of necessary accessories (sheeting screws	kg	1708.376	322.001	Three Hundred and Twenty-Two point Zero Zero One	550098.780	Five Lakh Fifty Thousand AND Ninety-Eight point Seven Eight	I have seen

			with washers, silicon sealant etc.), testing of materials etc. all complete as per drawing specification and direction of Engineer-in-charge.							
9	N/A	N/A	Dismantling different items and Site Cleaning, Providing Security Fencing & Removal of debris to a safe place as per direction of the Engineer-in-charge.	Item	20.000	10000.001	Ten Thousand point Zero Zero One	200000.020	Two Lakh point Zero Two	I have seen
10	N/A	N/A	Painting Works: Painting to M/S. angle Truss, G.I Pipe etc. two coat with synthetic enamel paint of best polarity and approved color, over a coat of priming including cleaning, finishing and polishing with sand paper and necessary scaffolding etc, all completed in all floors as per direction of Engineer-in-charge.	Item	25.000	2520.001	Two Thousand Five Hundred and Twenty point Zero Zero One	63000.025	Sixty-Three Thousand point Zero Two Five	I have seen
11	N/A	N/A	Fitting and fixing (MS Plate, Nut bolt, accessories etc) all MS Angle, MS Pipe in position etc all complete and accepted by the Engineer-in-charge.	Item	25.000	10000.001	Ten Thousand point Zero Zero One	250000.025	Two Lakh Fifty Thousand point Zero Two Five	I have seen
							Grand Total:	1851745.297	Eighteen Lakh Fifty-One Thousand Seven Hundred and Forty-Five point Two Nine Seven	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md Nazrul Islam on behalf of M/S. N. ISLAM & CO