

Section-6

BILL OF QUANTITIES

Name of work : Repair Maintenance & Painting work of of Boundary wall at Basar pol east side area DND Canal.


IFT No: 46.113.431.00.00.176.2024-25

Date:-05/05/2025


Sl No.	Basis of revised rate (PWD-2022)	Description of Items	Qty	Unit	Rate (Tk)	Amount (Tk)
(1)	(2)	(3)	(4)	(5)	(6)	(7=4x6)
CIVIL WORKS						
1	1.7	Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also cover clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge.	268.80	Sqm	218.001	58,598.669
2	32.1	Stripping of unserviceable plaster including racking out joints, cleaning etc.	570.28	Sqm.	31.00	17,678.680
3	15.1.1	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to wall both inner- and outer surface, finishing the corner and edges including washing of sand cleaning the surface, scaffolding and curing at least for 7 days, cost of water, electricity and other charges etc. all complete in all respect as per drawing and accepted by the Engineer. (Cement: CEM-II/A-M). Ground floor.	599.94	Sqm	315.001	188,981.700




M/S. ASHIK ENTERPRISE


Proprietor

Sl No.	Basis of revised rate (PWD-2022)	Description of Items	Qty	Unit	Rate (Tk)	Amount (Tk)
(1)	(2)	(3)	(4)	(5)	(6)	(7=4x6)
4	PWD-2.10.2	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	23.888	cum	1167.001	27,876.736
5	PWD-16.1.2	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	553.58	Sqm.	298.001	164,967.394
6	MP	Making Dhaka WASA Monogram on plaster surface of boundary wall	35.000	Nos	1,050.001	36,750.035



M/S. ASHIK ENTERPRISES


Proprietor

Sl No.	Basis of revised rate (PWD-2022)	Description of Items	Qty	Unit	Rate (Tk)	Amount (Tk)
(1)	(2)	(3)	(4)	(5)	(6)	(7=4x6)
7	MP	safety measure item (gum boot =4pairs, visible vest =4 nos , helmet =4 nos, hand gloves =4 pairs etc) . all complete and accepted by the Engineer-in-charge.	1.00	Item	2,500.001	2,500.001
Total Amount Tk.						497,353.215

Taka: Four Lac Ninety Seven Thousand Three Hundred Fifty Three Point Two One Five Taka Only.

Tender Price quoted by the Tenderer : The tenders shall quote in the following blanks space.	
5% below	4,72,405.554 (Four Lac Seventy ^{two} thousand Four hundred Eighty Five Point Five Five Four)
(Blank space provided for quoting.)	

Note:

- 1 Tenderers shall quote on the basis of "**Percentage (-5% to +5%) above, below or as per**" of the total estimated cost of the works, both in figures and in words in the blank space provided in the priced BQQ. Any change or modification by the Tenderer in the unit rate(s) or price(s) of the priced BQQ shall lead to rejection of that particular Tender. The price to be quoted in the Tender Submission Letter (From PW2b-1) shall be the total price of the Tender in accordance with (ITT clause-21.1)
- 2 It is suggested that the Tenderer uses these sheets of the BQQ in order to avoid any manipulation, distortion and inadvertent mistakes or omissions in course of preparing the Tender by the Tenderer.
- 3 Tenderer's profit, overheads, VAT and all other charges including corresponding incidental service charges for banking shall be deemed included in all the unit rates and prices in the BQQ against each basic item or activity and thus forth the total Tender Price quoted by the Teneers.

Syed Shihabur Rahman

Syed Shihabur Rahman
Executive Engineer
Saidabad Water Treatment Plant (Maintenance)
Dhaka WASA, Dhaka.

(Handwritten marks and signatures)

27/08/18

27/08/18

27/08/18

M/S. ASHIK ENTERPRISE
Proprietor