

Multi Scope

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	PWD-2023 (32.5.2)	Dismantling of plain concrete made of lime or cement and removal of debris to a safe distance.	Cum	11.790	1647.001	One Thousand Six Hundred and Forty-Seven point Zero Zero One	19418.141	Nineteen Thousand Four Hundred and Eighteen point One Four One	I have seen
2	Civil	DWASA SI-16.1	Renewing plaster in/c damp proof treatment with chemical Desalt S-01 & Foam Lub or equivalent as per specification after stripping off old plaster including cleaning scaffolding etc. complete as per direction of the Engineer.	sqm	43.680	187.001	One Hundred and Eighty-Seven point Zero Zero One	8168.203	Eight Thousand One Hundred and Sixty-Eight point Two Zero Three	I have seen
3	Civil	PWD-2023 (03.1.1)	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand leveling etc. complete and accepted by the Engineer-in-charge.	sqm	49.164	635.239	Six Hundred and Thirty-Five point Two Three Nine	31230.890	Thirty-One Thousand Two Hundred and Thirty point Eight Nine	I have seen
4	Civil	PWD-2023 (03.5.1)	Mass concrete (1:2:4) in foundation or in floor with cement sand (F.M. 1.2) and picked jhama brick chips including breaking of chips screening mixing laying compacting to required level and curing for at least 7 days including the supply of water electricity costs of tools & plants and other charges etc. all complete and accepted by	cum	9.900	10504.001	Ten Thousand Five Hundred and Four point Zero Zero One	103989.609	One Lakh Three Thousand Nine Hundred and Eighty-Nine point Six Zero Nine	I have seen

			Engineer-in-charge. (Cement: CEM-II / B-M) Mass concrete in foundation (1:2:4) with brick chips and local sand of F.M. 1.2.							
5	Civil	PWD-2023 (04.16)	125 mm brick works with first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making bond with connected walls including necessary scaffolding raking out joints cleaning and soaking the bricks for at least 24 hours before use and washing of sand curing at least for 7 days in all floors including cost of water electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M)	sqm	1.673	1408.001	One Thousand Four Hundred and Eight point Zero Zero One	2355.585	Two Thousand Three Hundred and Fifty-Five point Five Eight Five	I have seen
6	Civil	PWD-23-16.11	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container applying to wall and ceiling in 2 coats over a coat of brand specified primer or sealer elapsing specified time for drying/ recoating matt finish.	Sqm	414.498	213.001	Two Hundred and Thirteen point Zero Zero One	88288.488	Eighty-Eight Thousand Two Hundred and Eighty-Eight point Four Eight Eight	I have seen
7	Civil	DWASA SI-16.4	On exterior surface applying as per manufacturer instructions 3 coat of weather coat of approved quality and colour delivered from authorized local agent of the manufacturer in a sealed container complete in all respect in all floors and accepted by the Engineer.	sqm	27.881	150.001	One Hundred and Fifty point Zero Zero One	4182.177	Four Thousand One Hundred and Eighty-Two point One Seven Seven	I have seen
8	Civil	PWD-23 16.3.1	Standard synthetic enamel paint of approved best quality and color having water resisting properties and resistance properties against fungi fading & flaking delivered	Sqm	118.216	229.001	Two Hundred and Twenty-Nine point Zero Zero One	27071.582	Twenty-Seven Thousand AND Seventy-One point Five Eight Two	I have seen

			from authorized local agent.							
9	N/A	M/R	Skylight Glass	each	5.000	300.001	Three Hundred point Zero Zero One	1500.005	One Thousand Five Hundred point Zero Zero Five	I have seen
10	N/A	M/R	Collapsible Gate repair accepted by the Engineer.	each	1.000	2000.001	Two Thousand point Zero Zero One	2000.001	Two Thousand point Zero Zero One	I have seen
11	N/A	M/R	Old Rack rep & painting accepted by the Engineer.	Nos	8.000	3000.001	Three Thousand point Zero Zero One	24000.008	Twenty-Four Thousand point Zero Zero Eight	I have seen
12	E/M	DWASA SI-19.2	Surface Channel Wiring for the following PVC insulated and sheathed stranded cable (BYM) & green/white colored PVC insulated ECC wire (BYA) through minimum 1 mm thick PVC channel complete with fixing materials and others accessories etc. as required and mending the damaged good.1c-2x2.5 sq mm	m	20.000	174.001	One Hundred and Seventy-Four point Zero Zero One	3480.020	Three Thousand Four Hundred and Eighty point Zero Two	I have seen
13	E/M	PWD-2022 EM-21.1.1.1	Supply Fitting fixing 56 inch ceiling Fan	each	2.000	3914.001	Three Thousand Nine Hundred and Fourteen point Zero Zero One	7828.002	Seven Thousand Eight Hundred and Twenty-Eight point Zero Zero Two	I have seen
14	E/M	PWD-2022 EM-4.13.3	Supply Fitting fixing of Fan Regulator	each	2.000	593.001	Five Hundred and Ninety-Three point Zero Zero One	1186.002	One Thousand One Hundred and Eighty-Six point Zero Zero Two	I have seen
15	E/M	PWD-2022 EM-4.11.1.2	Supply Fitting fixing Universal Combind Switch Soket	each	5.000	421.001	Four Hundred and Twenty-One point Zero Zero One	2105.005	Two Thousand One Hundred and Five point Zero Zero Five	I have seen
16	E/M	PWD-2022 EM-4.12.3.4	Supply Fitting fixing of 4-gang switch	each	2.000	323.001	Three Hundred and Twenty-Three point Zero Zero One	646.002	Six Hundred and Forty-Six point Zero Zero Two	I have seen

17	E/M	M/R	Supply Fitting fixing of (25W) LED Tube Light	each	4.000	1000.001	One Thousand point Zero Zero One	4000.004	Four Thousand point Zero Zero Four	I have seen
18	E/M	PWD-2023 EM-1.1.1.1	Light Point	p/point	4.000	1203.001	One Thousand Two Hundred and Three point Zero Zero One	4812.004	Four Thousand Eight Hundred and Twelve point Zero Zero Four	I have seen
19	E/M	PWD-2022 EM-1.1.1.2	Fan Point	p/point	2.000	1203.001	One Thousand Two Hundred and Three point Zero Zero One	2406.002	Two Thousand Four Hundred and Six point Zero Zero Two	I have seen
20	E/M	M/R	Labour for cleaning and removal of waste rubbish and re-arrangement of goods.	Each	35.000	800.001	Eight Hundred point Zero Zero One	28090.035	Twenty-Eight Thousand point Zero Three Five	I have seen
21	E/M	M/R	Supply of different types of tools use in Water Supply maintenance including SCADA.	LS	1.000	55830.773	Fifty-Five Thousand Eight Hundred and Thirty point Seven Seven Three	55830.773	Fifty-Five Thousand Eight Hundred and Thirty point Seven Seven Three	I have seen
22	E/M	M/R	Removing of Wastage (Truck)	each	5.000	5000.002	Five Thousand point Zero Zero Two	25000.010	Twenty-Five Thousand point Zero One	I have seen
							Grand Total:	447498.548	Four Lakh Forty-Seven Thousand Four Hundred and Ninety-Eight point Five Four Eight	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Asadul Karim on behalf of Multi Scope