

Office of the Executive Engineer

MODS Zone – 8, Dhaka WASA
Notunbazar Buster Pump compound
Baridhara, Dhaka.

Estimate

Name of Work:- Changing & Maintenance of Flush Door Shutter & Maintenance of Ozukhana at MODS Zone-8 Office, Dhaka WASA.


SL. NO	Basis of Rate	Description of item work	Qty	Unit	Rate	Total Amount (Tk)
1	PWD Rate Schedule 2022 12.8.3	Supplying, fitting and fixing of 38mm thick wooden grooved single panel flush door shutter having door frame section 150mm x 62mm weighing 16.7kg/sqm with 4nos 100mm long, 3mm thick hinge, 1 no round lock, 2nos 150mm long handle, hinged cleats and carrying the same to the site and local carriage etc. All complete in all floors and accepted by the Engineer-in-charge.	9.000	each	23065.000	207585.000
2	PWD Rate Schedule 2022 12.2	Supplying, fitting and fixing hydraulic door closer (big size) of approved quality including all necessary tools and accessories etc. all complete and accepted by the Engineer-in-charge.	9.000	each	2684.000	24156.000
3	PWD Rate Schedule 2022 32.5.1.2	Supplying, fitting and fixing of best quality country made 12 mm bib cock made from copper or copper alloy, chromium plated. The faucet conforms BDS EN 200:2009. The faucet tap shall be free from any leakage, permeation and other abnormalities. The water hammer value shall be 1.47 MPa or under. The faucet after it has been operated 100000 times it shall be free from a seat-leakage and shall satisfy the reverse flow preventing performance. The inside and outside surfaces of the faucet shall be smooth and be free from blowholes, fissures, remarkable flows or injurious defects. The chromium plating on the faucet shall be of class 2 grade 1. The final coating should be done with chromium of minimum 0.1 micron. The faucet shall be made leak proof and fixing in position with selected tape etc. all complete approved and accepted by the Engineer-in-charge. Round headed CP Conceal Bib Cock short body (Essco/ coaster/ star/ diamond/ delux/ deco/ orbed/ delin/ triple/ master/ classic headed or similar head)	3.000	nos.	1172.000	3516.000
4	PWD Rate Schedule 2022 32.6.2	Supplying, fitting and fixing best quality heavy type 19 mm dia and 300 mm long hasp bolt including cutting grooves in door shutter and frames, screws etc. all complete approved and accepted by the Engineer-in-charge. Brass Hasp Bolt	9.000	each	552.000	4968.000

SL. NO	Basis of Rate	Description of item work	Qty	Unit	Rate	Total Amount (Tk)
5	PWD Rate Schedule 2022 3.5	Supplying, fitting and fixing of best quality magnetic door holder of approved quality including all necessary tools and accessories all complete and accepted by the Engineer-in-charge.	9.000	each	374.000	3366.000
6	PWD Rate Schedule 2022 03.5.2	Taking out of old & unserviceable wooden chowkat/ door or window frame	9.000	each	328.000	2952.000
7	PWD Rate Schedule 2022 7.1	Taking out and refitting of wooden shutter after easing excluding the cost of wood	9.000	each	450.000	4050.000
8	PWD Rate Schedule 2022 07.1.1	Offset Patter match High-Quality Floor Carpet Extra Washable Waterproof	200	sft	200.000	40000.000
9	PWD Rate Schedule 2022 4.16	Mortise lock with Satin Stainless Steel Solid lever handle (Yale handle model no- YSL804, Dorset model no- PR 10 (SS) / Hafele model no- 903.92.636 solid lever handle or equivalent)	1	each	6000.000	6000.000
10	L/S	Cleaning of Debris, Painting Broken wall & Site Cleaning	1	L/S	2000.000	2000.000
Total Tk.=						298593.000

In Word = Two lac Ninety Eight Thousand Five Hundred & Ninety Three Taka only.


 26/05/25
 শেখ আহমেদ সাহিদ সাবি আল
 উপ-সহকারী প্রকৌশলী
 মডস জোন-৮
 ঢাকা ওয়াশা।


 26.05.25
 মোঃ গোলাম মোস্তফা বন্দকার
 উপ-বিভাগীয় প্রকৌশলী
 মডস জোন-৮, ঢাকা ওয়াশা।


 26/05/25
 অনুপম কুমার মন্ডল
 নির্বাহী প্রকৌশলী
 মডস জোন-৮
 ঢাকা ওয়াশা।