

Sikder Construction										
Priced Bill of Quantities (BOQ)										
Unit Rate Basis										
Estimate by the Procuring Entity										
Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	civil	PWD-2022-32.1	Stripping of unserviceable plaster including racking out joints, Cleaning etc.	P/sqm	430.380	31.001	Thirty-One point Zero Zero One	13342.210	Thirteen Thousand Three Hundred and Forty-Two point Two One	I have seen
2	civil	PWD-2022-15.1.1	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	P/sqm	430.380	299.001	Two Hundred and Ninety-Nine point Zero Zero One	128684.050	One Lakh Twenty-Eight Thousand Six Hundred and Eighty-Four point Zero Five	I have seen
3	civil	PWD-2022-02.10.1	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	P/cum	32.530	1088.001	One Thousand AND Eighty-Eight point Zero Zero One	35392.673	Thirty-Five Thousand Three Hundred and Ninety-Two point Six Seven Three	I have seen
4	civil	PWD-2022-02.10.1	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks (BDS-208) including preparation of bed and filling the interstices with local sand, leveling etc. complete and accepted by the Engineer-in-charge	P/sqm	18.590	518.001	Five Hundred and Eighteen point Zero Zero One	9629.639	Nine Thousand Six Hundred and Twenty-Nine point Six Three Nine	I have seen
5	civil	PWD-2022-03.5.2	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing,	P/cum	1.380	8840.001	Eight Thousand	12199.201	Twelve Thousand	I have seen

			laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge.(Cement: CEM-II/B-M) Mass concrete in floor (1:2:4) with cement, brick chips and sand of F.M. 1.2				Eight Hundred and Forty point Zero Zero One		One Hundred and Ninety- Nine point Two Zero One	
6	civil	PWD-2022-16.2.1	Interior standard acrylic emulsion paint (plastic or matt finish) of approved best quality and colour delivered from authorized local agent of the manufacturer (Berger robbialac plastic emulsion/Asian apcolite plastic emulsion or equivalent brand) in a sealed container; applying to interior wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of interior sealer of specified brand on prepared surface; then applying 1 coat of interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of interior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	P/sqm	301.170	258.001	Two Hundred and Fifty-Eight point Zero Zero One	77702.161	Seventy- Seven Thousand Seven Hundred and Two point One Six One	I have seen
7	civil	PWD-22: 16.1.1	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resisting properties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer (Berger Weather Coat Antidirt Long Life/ Elite Master Coat/ Asian Apex Ultima or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	P/sqm	301.170	274.001	Two Hundred and Seventy- Four point Zero Zero One	82520.881	Eighty-Two Thousand Five Hundred and Twenty point Eight Eight One	I have seen
8	civil	WASA-2011	On exterior surface applying as per manufacturer instructions 3 coat of weather coat of approved quality and colour delivered from authorized local agent of the manufacturer in a sealed container complete in all respect in all floors and accepted by the Engineer.	P/sqm	511.810	150.001	One Hundred and Fifty point Zero Zero One	76772.012	Seventy-Six Thousand Seven Hundred and Seventy-Two point Zero One Two	I have seen
9	civil	PWD-22: 16.3.1	"Cleaing sludges & night soil from septic tank removing to a safe place/distance without affecting environment. 10 user septic tank"	P/No	2.000	2393.001	Two Thousand Three Hundred and Ninety-Three point Zero Zero One	4786.002	Four Thousand Seven Hundred and Eighty-Six point Zero Zero Two	I have seen

10	civil	PWD-19.2.1 (Estimated)	Repairing and Maintenance of M.S Gate including Cutting welding, grinding, re-fixing and fitting-fixing of materials and other works etc. all complete as per direction of Engineer in Charge.	P/Sqm	3.570	6667.001	Six Thousand Six Hundred and Sixty-Seven point Zero Zero One	23801.194	Twenty-Three Thousand Eight Hundred and One point One Nine Four	I have seen
11	civil	PWD-22:1.1.1.1	Surface channel wiring for the following point looping at the switch board with earth terminal with 1C-2x1.5 sqmm PVC insulated and sheathed stranded cable (BYM) and same size PVC insulated ECC(BYA) (Green / White Color) including circuit wiring with 1C-2x2.5 sqmm PVC insulated and sheathed stranded cable (BYM) & same size PVC insulated ECC(BYA) Green / White color through minimum 1 mm thick PVC channel complete with 18 SWG GP sheet / PVC switch board (preferably concealed) with 3mm thick ebonite sheet cover, circular box, without switch, fixing materials, other accessories etc. as required and mending the damages good. All electrical contacts shall be of brass / copper connected through connector or soldering (no twisting shall be allowed) and cables shall be manufactured and tested according to relevant IEC / BDS / BS / VDE standards and as per detailed specification mentioned in Annexure-1. The work shall be carried out as per direction & approval of the Engineer.Light / Fan/exhaust or wall bracket fan point	P/Point	4.000	1203.001	One Thousand Two Hundred and Three point Zero Zero One	4812.004	Four Thousand Eight Hundred and Twelve point Zero Zero Four	I have seen
12	civil	PWD-22:16.3.1	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in sealed container having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brush / roller/spray in 2 coats over single coat anticorrosive coating including cleaning. drying. making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer in charge	P/sqm	42.600	229.001	Two Hundred and Twenty-Nine point Zero Zero One	9755.443	Nine Thousand Seven Hundred and Fifty-Five point Four Four Three	I have seen
13	civil	Lumsum	Site cleaning work for removing all debris from the site with contractor own all complete as per Direction of the Engineer in Charge.	P/No	2.000	5000.351	Five Thousand point Three Five One	10000.702	Ten Thousand point Seven Zero Two	I have seen
							Grand Total:	489398.172	Four Lakh Eighty-Nine Thousand Three Hundred and Ninety-Eight point One Seven Two	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Kamal Sikder on behalf of Sikder Construction