


Office of the Executive Engineer
Padma Water Treatment Plant
Jashaldia, Louhojong, Munshigonj.
Dhaka WASA.

Subject: Repair maintenance of approach road at WTP to damla primary school.

Section 6 Bill of Quantities						
Sl. No.	Description of items	Rate Basis	Quantity	Unit	Rate (Tk/Unit)	Amount TK
1	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	PWD Code 02.10.1	45.00	cum	635.00	28575.00
2	Earth filling for trenches and plinth in 150 mm layer with earth available within 90 m of the building site to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) including carrying watering, leveling, dressing and compacting to a specified percentage each layer up to finished level etc. all complete and accepted by Engineer-in-charge.	PWD rate C, Item 02.13	45.00	cum	149.00	6705.00
3	Supply of GO Bag , Size: 30"x40"	Approved rate	25.00	no	360.00	9000.00
4	Site cleaning work	LS	1	item	5000.00	5000.00
	In Total (in figure)					49280.00
In Total (in Word): Forty nine thousand two hundred eighty only.						


16.06.25
Amit Bishwas
Sub-Assistant Engineer
Padma Water Treatment Plant
Dhaka WASA


16/6/25
Md. Forhad Hossain
Assistant Engineer
Padma Water Treatment Plant
Dhaka WASA


16.06.25
Gazi Asrib Bin Salam
Executive Engineer
Padma Water Treatment Plant
Dhaka WASA