

M/S Anika Builders**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	N/A	N/A	Installation of net with bamboo support for protection of debris at intake tower of Buriganga river. All equipments/materials including Bamboo, Net, wiring, stone, labour, diver, safety equipment (PPE), Site cleaning, tripod and any other equipments required for this works will be provided by the contractor. Installation of 3-4 inch dia Barak bamboo (Length 35 ft each) in front of intake tower of Buriganga river vertically, horizontally and inclined position. All costs including bamboo, rope, wire nail, labour, diver are considered here.	Each	282.000	845.001	Eight Hundred and Forty-Five point Zero Zero One	238290.282	Two Lakh Thirty-Eight Thousand Two Hundred and Ninety point Two Eight Two	I have seen
2	N/A	N/A	Fitting Fixing Nylon rope net (Mesh size-50mm x 50mm, Rope dia size-2.5mm-3mm) with installed bamboo support. All costs including net, rope, wire nail, labour, diver are considered here.	sqm	594.570	355.001	Three Hundred and Fifty-Five point Zero Zero One	211072.945	Two Lakh Eleven Thousand AND Seventy-Two point Nine Four Five	I have seen
3	N/A	N/A	Cleaning of (1) Five manual screen, (2) inside & out side chamber and (3) 800 mm dia pipe line of intake tower of Chandnighat water treatment plant by skilled divers. The divers will be well equipped with SCBA(Self contained breathing apparatus) and any others equipment necessary for working under water. All cleaning works as mentioned above will be treated as one item.	Item	1.000	40049.981	Forty Thousand AND Forty-Nine point Nine Eight One	40049.981	Forty Thousand AND Forty-Nine point Nine Eight One	I have seen

