




Office of the Executive Engineer
Padma Water Treatment Plant
Jashaldia, Louhojong, Munshigonj.
Dhaka WASA.

Subject: Repair maintenance of approach road at WTP Main gate to damla Road.

Section 6 Bill of Quantities						
Sl. No.	Description of items	Rate Basis	Quantity	Unit	Rate (Tk/Unit)	Amount TK
1	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	PWD Code 02.10.1	4.76	cum	1087.930	5180.619
2	Earth filling in foundation trenches and plinth in 150 mm layer with earth available within 90 m of the building site to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) including carrying watering, leveling, dressing and compacting to a specified percentage each layer up to finished level etc. all complete and accepted by Engineer-in-charge.	PWD rate 02.13	4.76	cum	206.910	985.286
3	Brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:4) in exterior walls including filling the interstices with mortar, raking out joints, cleaning and soaking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7 days etc. all complete including cost of water, electricity and other charges (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor	PWD rate 04.3	2.78	cum	8419.600	23387.778
4	Supply of GO Bag , Size: 30"x40"	A.R.	325	nos	50.000	16250.000
5	Site cleaning work	LS	1	item	4000.000	4000.000
In Total (in figure)						49803.683
In Total (in Word): Forty nine thousand eight hundred three point six eight three only.						


Md. Mehedi Hasan
Sub-Assistant Engineer
Padma Water Treatment Plant
Dhaka WASA


Mohammed Soheli Rana
Assistant Engineer
Padma Water Treatment Plant
Dhaka WASA


Gazi Asrib Bin Salam
Executive Engineer
Padma Water Treatment Plant
Dhaka WASA