

Office of the Executive Engineer
Savar-Keraniganj Wellfield Plant
Dhaka WASA

Name of the Work: Water treated sludge remove at IRP-2, Savar-keraniganj well field plant.

Item No.	Group	Item Code.	Description of Items of Works	Unit	Quantity	Unit rates or prices	Amount
1	civil	32.5.2	Dismantling of plain concrete made of lime or cement and removal of debris to a safe distance.	cum	5.750	3928.001	22586.006
2	civil	517.61	One layer brick flat soling in foundation or in floor with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling	sqm	23.000	517.61	11905.03
3	civil	03.5.1	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II/B-M) Mass concrete in foundation (1:2:4) with brick chips and local sand of F.M. 1.2.	cum	11.45	8885.741	101741.734
4	civil	02.9	Removing sludge or semi-liquid clay/substances etc not suitable for pumping out or carrying by head load from the bottom of any marshy land, lake, ditch, pond by mixing fine local sand of minimum F.M. 0.8 to a proportion such that it can be carried to an intermediate point of disposal and cutting the same including stacking and spreading properly on a suitable place to dry in the sun for a certain days and dispose the dried sludge or clay to a safe distance etc. complete and accepted by Engineer-in-charge subject to submit method statement to the engineer in charge for carrying out the works including ultimate disposal of the sludge under this item for approval. However, engineer's approval shall not relieve the Contractor of his responsibilities and obligations under the contract.	cum	338.310	1053.85	356527.994
Total:							492760.764
(Four Lakh Ninety Two Thousand Seven Hundred Sixty Point Seven Six Four)							

Sub-Assistant Engineer
SKWP,Dhaka WASA

Assistant Engineer
SKWP,Dhaka WASA

Executive Engineer
SKWP,Dhaka WASA