

ঢাকা পানি সরবরাহ ও পয়ঃ নিষ্কাশন কর্তৃপক্ষ

Office of the Executive Engineer

Field Maintenance Division-2, Dhaka WASA.

শেখ হাসিনার মূলনীতি
গ্রাম শহরের উন্নতি

ওয়ার্ড

Sub: Shifting and replacement of HT pole & HT cable at Dhamal court-1 DTW under MODS Zone 10, DWASA.

SL No	Description of Item	Rate Basis	Unit	Qty	Rate	Price(TK)
1	Disconnection & reconnection of H.T line by concerned DESCO including all expenditures related to the item. DC/RC Fee shall be paid by concern MODS Zone on behalf of FMD-2, with monthly electricity bill.	As per DESCO/DPDC	Per job	As per required	DWASA Power Budget	
2	Earth work in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead. Size: 9.75mX0.61X1.52=9.04cum	PWD-RS-22 P-109, CW SL-02.1.2	Cum	9.04	168	1518.720
3	Earth filling in foundation trenches and plinth in 150 mm layer with earth available within 90 m of the building site to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) including carrying, leveling, dressing and compacting to a specified percentage each layer upto finished level. all complete and accepted by Engineer-in charge. Size: 9.75mX0.18X1.52=2.67cum	PWD-RS-22 P-110, CW SL-02.13	cum	2.67	207	552.690
4	Sand filling in foundation trenches and plinth with sand having minimum F.M.0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (modified proctor test) by Emmering each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge. Size: 9.75mX0.42X1.52=6.22cum	PWD-RS-22 P-110, CW SL-02.10.1	Cum	6.22	1088	6767.360
5	Supply & installation of heat shrink termination kit outdoor/indoor use complete with DIN lugs earth connection hardware & cable preparation kit(indoor & out door) at the point of cable termination for 11kv 3 core PVC insulated & PVC sheathed & armored/non armored cable of the following size: Size-3x50 mm2, as per direction of the engineer in charge.	Wasa-R.s-20011,SL-48	Per kit	1	10390.000	10390.000
6	Providing & installation of heat shrink joint kit complete with DIN ferrules, cable preparation kits at the point of jointing of cables for 11kv 3 core PVC sheathed armored/non armored cables of the following size: Size-3x50 mm2, as per direction of the engineer in charge.	PWD-RS-18 P-105,SL-4.22.(!!)	Per kit	1	18611.000	18611.000
7	Installation and connection of all equipment of the sub station by skilled and experienced electricians using necessary materials such as plastic tape, PIB Tape, cable socket etc.	Wasa-R.s-2002 P 54 SL-13	per job	1	9770	9770.000
Total (Taka)						47609.770
In word: Forty-seven thousand six hundred nine point seven seven zero taka only						

24.07.24
মোঃ শরীফুল ইসলাম
উপ-সহকারী প্রকৌশলী
এফ.এম. বিভাগ-২, ঢাকা ওয়াসা

24.07.24
মোঃ মাহবুবুল হক প্রামাণিক
সহকারী প্রকৌশলী
এফ.এম. বিভাগ-২, ঢাকা ওয়াসা

24/07/2024
শেখ আরিফ রহমান জিহু
নির্বাহী প্রকৌশলী