

Barisal enterprise

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	-	N/A	Mobilization, Demobilization and cleaning of the work site, removal of debris and other materials from inside the site, restoration of the finished ground surface, filling the surrounding ground surface removing, contractors materials shades, machinery etc from the work site after completion of the works up to satisfaction of the Engineer-in-charge.	L/S	1.000	12950.001	Twelve Thousand Nine Hundred and Fifty point Zero Zero One	12950.001	Twelve Thousand Nine Hundred and Fifty point Zero Zero One	I have seen
2	-	N/A	Erection and maintenance of site office and removal the same after completion of work in accordance with the conditions of contract. "Engineer's site office of minimum 10 sqm plinth area with providing furniture, first aid-box, safety helmet, consumables, stationeries etc	L/S	1.000	30000.001	Thirty Thousand point Zero Zero One	30000.001	Thirty Thousand point Zero Zero One	I have seen
3	-	N/A	Earth work in excavation or re-excavation of Khal/ U-type RCC Channel by using Amphibious Excavator and soil carrying burge in all kinds of soils up to the required depth width and lead & lift provided in the layout, construction of temporary bench mark, including the scooping out of all kinds of sludge, sewage, loose soil, debris, jungles, shrub, floating solid waste cutting of tree (if necessary) etc. lead & lift up to required height all complete as per drawing, specification and direction of the E/C.	Cum	3799.100	442.001	Four Hundred and Forty-Two point Zero Zero One	1679205.999	Sixteen Lakh Seventy-Nine Thousand Two Hundred and Five point Nine Nine	I have seen
4	-	N/A	Removing sludge, sewerage, loose soil, debris, jungles, shrub, floating solid waste/ substance etc from the working site that is Khal/ U-type RCC channel up to the Matuail DSCC dumping yard/	Cum.	3799.100	462.001	Four Hundred and Sixty-Two point Zero Zero One	1755187.999	Seventeen Lakh Fifty-Five Thousand One Hundred and Eighty-	I have seen

			Amin Bazar DNCC Dumping yard/ Pagla WASA Dumping yard or any other suitable place carrying by using 10 wheeler Dump Truck (Water tight) etc complete as per direction of the Engineer in charge.						Seven point Nine Nine Nine	
5	-	N/A	Supplying, carrying, shalbolah of 150mm (av.) dia & 100mm (av.) dia and placing, driving to required depth in proper position by using monkey hammer or any other approved method & fitting fixing in proper position etc., coloring the same two coats with where necessary as per drawing specification and direction of the E/c. i) Cost of 150mm (av.) shalbolah	Rm.	1260.000	629.001	Six Hundred and Twenty-Nine point Zero Zero One	792541.260	Seven Lakh Ninety-Two Thousand Five Hundred and Forty-One point Two Six	I have seen
6	-	N/A	ii) Cost of 150mm (av.) shalbolah driving	Rm.	828.000	121.001	One Hundred and Twenty-One point Zero Zero One	100188.828	One Lakh One Hundred and Eighty-Eight point Eight Two Eight	I have seen
7	-	N/A	Supplying, cleaning, straightening & fitting fixing the drum sheet in position with shalbolah for protection of loose sludge, slushy earth, derbies etc. all complete as per direction of Engineer-in-charge.	Sqm.	216.000	575.001	Five Hundred and Seventy-Five point Zero Zero One	124200.216	One Lakh Twenty-Four Thousand Two Hundred point Two One Six	I have seen
8	-	N/A	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	Cum.	480.000	635.001	Six Hundred and Thirty-Five point Zero Zero One	304800.480	Three Lakh Four Thousand Eight Hundred point Four Eight	I have seen
9	-	N/A	125 mm brick work with first class bricks with cement sand (F.M. 1.2) mortar (1:6) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all	Sqm.	63.000	948.001	Nine Hundred and Forty-Eight point Zero Zero One	59724.063	Fifty-Nine Thousand Seven Hundred and Twenty-Four point Zero Six Three	I have seen

			Engineer-in-charge. (Cement: CEM-II/A-M) In ground floor							
10	-	N/A	Providing minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) ground floor.	Sqm.	126.000	243.001	Two Hundred and Forty-Three point Zero Zero One	30618.126	Thirty Thousand Six Hundred and Eighteen point One Two Six	I have seen
11	-	N/A	Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer (Berger weather coat smooth/ Elite smooth exterior/ Asian apex weather coat or equivalent brand) in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of exterior sealer of specified brand on prepared surface; then applying 1 coat of exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint by spreading with brush/roller/spray machine & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	Sqm.	126.000	238.001	Two Hundred and Thirty-Eight point Zero Zero One	29988.126	Twenty-Nine Thousand Nine Hundred and Eighty-Eight point One Two Six	I have seen
12	-	N/A	Traffic Management at the loading point with labour and supply of safety measure Item Etc. all complete as per E/C	Item	1.000	50000.001	Fifty Thousand point Zero Zero One	50000.001	Fifty Thousand point Zero Zero One	I have seen
							Grand Total:	4969405.100	Forty-Nine Lakh Sixty-Nine Thousand	

[View Form](#)

Four
Hundred
and Five
point One

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Furkan on behalf of Barisal enterprise

Barisal enterprise**Tenderer's Quoted Price****Tenderer's Quoted Price**

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
4969405.100	-5.000	4720934.845	Forty-Seven Lakh Twenty Thousand Nine Hundred and Thirty-Four point Eight Four Five
	Grand Total:	4720934.845	Forty-Seven Lakh Twenty Thousand Nine Hundred and Thirty-Four point Eight Four Five

This Tenderer's Quoted Price is Electronically Signed by Mr. Md. Furkan on behalf of Barisal enterprise