

Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water In Front Of House no-25, Road no-10,Block no-K & House no-15/16, Road no-10, Aftab Nagar (DMA-806) under MODS Zone-8, Dhaka WASA.

Sl. No.	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	160 mm dia HDPE Pipe	7.00	P/M			Supply by Sub store
2	160 mm dia HDPE Sleeve E.F	2	Nos	5000.00	10,000.00	
3	Earth work: $(3.66*7.5*1.52)=41.72$ cum	41.72	Cum	149.00	6216.28	
4	Supply, depositing and compaction of fine sand (FM 0.8) bedding surrounding and above pipe $(3.66*7.5*1.52)=41.72$ cum	41.72	Cum	503.00	20985.16	
5	Mechanics Charge	1	P/Person	1000.00	1000.00	
6	Daily Labour	9	P/Person	800.00	7200.00	
7	Hire charge of de-watering pump	2	P/Day	1862.00	3724.00	
Total (Tk.)					49125.44	
Say Total (Tk.)					49125.00	

In words: Forty Nine Thousand One Hundred Twenty Five Taka Only.


21.09.23
আবুল কালাম আল মনির
উপ-সহকারী প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াসা।


21.09.23.
মোঃ মোস্তফা
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।


21/09/23
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।