


8

**Office of the Executive Engineer
MODS Zone-2, Dhaka WASA
144/1, water Works Road
Dhaka-1211**


Name of Work : Cleaning & Maintenance of Soak Wells at 10 Nos Pump House Compounds Under MODS Zone-2 Dhaka WASA
(package No-2)

Sl. No	Basis of rate	Description of Item	Qty.	Unit	Rate (Tk)	Amount (Tk.) (4x6)
1	2	3	4	5	6	7
1	PWD-24.1.1	Excavation in all materials except rock for the construction of main sewer manholes to the full depth and maximum dimensions required by the Specification in the various depth ranges give below. All in accordance With the Technical Specification and standard detail Drawings. The rate include for all necessary de-watering to maintain the excavation in a dry condition at all times. Preparation of the bottom of the excavation materials. a) For Depth not exceeding 1.5m	38.532	Cum	201.001	7,744.973
2	PWD-2.14	Clearing and disposing of excavated earth from the site by truck or any other means to a place within 30 km radius of the city or town area including loading, uploading at both ends, leveling and dressing the carried earth etc. complete and accepted by the engineer.	30.826	Cum	756.001	23,304.192
3	PWD-4.1	Brick work for the walls of manhole and service pit, at any req. depth all in accordance with the technical specification and standard detail drawings the rate to include for the supply of first class bricks, the preparation of sand cement mortar including the supply of all materials and flush pointing to the face of the brickwork wall	30.155	Cum	9,140.001	275,621.189
4	PWD-32.104	Plaster work :-Minimum 12mm thick cement plaster (1:4) with fresh cement to wall both inner and outer surface finishing the corner edge including washing of sand cleaning the surface scaffolding and curing at least for 7 days etc all complete.	131.63	sqm	498.001	65,552.418
5	PWD-32.88	Clearing sludges & night soil from RCC soil pipe & sewer line	91.46	Meter	111.000	10,152.439
6	PWD-32.73.1	Clearing sludges & night soil from Inspection pit	10.00	Nos	525.000	5,250.000
7	Approved Rate	Sewer Cleaning Labour for cleaning work from Soak wells	50.00	Nos	1,000.001	50,000.050
8	L/S	Manhole cover Fitting & Fixing	7.00	Nos	2,500.001	17,500.007
9	Approved Rate	Van rental with Puller for Carrying Sewer waste Packet	40.00	Nos	1,000.001	40,000.040
Total Tk.=						495,125.308
Say TK=						495126.00

In word:(Four Lac Ninety Five Thousand One Hundred Twenty Six Taka) Only.


26/10/20
Sub-Assistant Engineer
MODS Zone-2
Dhaka WASA


26/10/20
Assistant Engineer
MODS Zone-2
Dhaka WASA


25/10/20
Executive Engineer
MODS Zone-2
Dhaka WASA
মোহাম্মদ নজরুল ইসলাম
নির্বাহী প্রকৌশলী
মডস জোন-২, ঢাকা ওয়াসা।