

M/S MANNA & COMPANY

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Civil	PWD -18 32.6.1.2	Dismantle of R.C.C slab/road and Removal of debris to a safe distance	Cum	10.686	2790.000	Two Thousand Seven Hundred and Ninety	29813.940	Twenty-Nine Thousand Eight Hundred and Thirteen point Nine Four	I have seen
2	Civil	PWD -18 04.1	Brick works with first class bricks in cement sand (F.M. of sand 1.2) mortar (1:6) in foundation and plinth filling the joints/interstices fully with mortar racking out the joints cleaning and soaking the bricks at least for 24 hours before use and curing at least for 7 days etc. all complete including cost of water electricity and other charges and accepted by the Engineer.	Cum	5.343	6040.000	Six Thousand AND Forty	32271.720	Thirty-Two Thousand Two Hundred and Seventy-One point Seven Two	I have seen
3	Civil	PWD -18 15.2	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to plinth wall (1:4) with cement up to 150 mm below ground level with neat cement finishing including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity and other charges etc. all complete in all respect as per drawing and accepted by the Engineer.	Cum	181.334	280.000	Two Hundred and Eighty	50773.520	Fifty Thousand Seven Hundred and Seventy-Three point Five Two	I have seen
4	Civil	Pre-Approved Rate	Re-Fitting & fixing of manhole cover by cement concrete. Supply will be contractor without CI cover, all complete and accepted by the Engineer	Cum	50.000	2000.000	Two Thousand	100000.000	One Lakh	I have seen
5	Civil	Pre-Approved	Manhole Cleaning by Sewer cleaner etc. all	Each	100.000	1000.000	One Thousand	100000.000	One Lakh	I have

		Rate	complete and accepted by the Engineer						seen
6	Civil	DWASA S-63 SL.No.-5	Bailing out of all water from pipe line trench with supply of de-watering pump required size including supplying of fuel lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc.	Day	50.000	1862.000	One Thousand Eight Hundred and Sixty- Two	93100.000	Ninety- Three Thousand One Hundred I have seen
7	Civil	PWD - 02.14	Clearing and disposing of wastagedismantaliad rocksewer sludge etc from work site by truck or any other means to a place within 30 km radius of the city or town area including loading unloading at both ends leveling and dressing the carried earth etc. complete accepted by the Engineer.	cum	23.184	539.000	Five Hundred and Thirty- Nine	12496.176	Twelve Thousand Four Hundred and Ninety-Six point One Seven Six I have seen
8	Civil	Pre- Approved Rate	Safety barricade by bamboo flag lighting etc.all complete and accepted by the Engineer.	Each	50.000	1000.000	One Thousand	50000.000	Fifty Thousand I have seen
9	Civil	Pre- Approved Rate	Gurd/curing man all complete and accepted by the Engineer.	Sqm	50.000	500.000	Five Hundred	25000.000	Twenty- Five Thousand I have seen
							Grand Total:	493455.356	Four Lakh Ninety- Three Thousand Four Hundred and Fifty- Five point Three Five Six

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Muntasir Manna on behalf of M/S MANNA & COMPANY

M/S MANNA & COMPANY**Tenderer's Quoted Price****Tenderer's Quoted Price**

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
493455.356	-5.000	468782.588	Four Lakh Sixty-Eight Thousand Seven Hundred and Eighty-Two point Five Eight Eight
	Grand Total:	468782.588	Four Lakh Sixty-Eight Thousand Seven Hundred and Eighty-Two point Five Eight Eight

This Tenderer's Quoted Price is Electronically Signed by Mr. Muntasir Manna on behalf of M/S MANNA & COMPANY