

NURJAHAN ENTERPRISE

Price and Delivery Schedule for Goods (Form e-PG2-2A)

Price and Delivery Schedule for Goods

Item No.	Description of Item	Measurement Unit	Quantity	Point of Delivery	Delivery Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	" Supply of 110 mm dia HDPE Pipe "	m	204.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	1000.001	One Thousand point Zero Zero One	204000.204	Two Lakh Four Thousand point Two Zero Four
2	Supply of 110 mm End Cap	nos	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	25000.011	Twenty- Five Thousand point Zero One One	25000.011	Twenty- Five Thousand point Zero One One
3	"Supply of HDPE SLEEVE (EF) 110 mm "	nos	30.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	2000.001	Two Thousand point Zero Zero One	60000.030	Sixty Thousand point Zero Three
4	Supply of 160 mm DI Dresser Coupler	nos	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	2100.001	Two Thousand One Hundred point Zero Zero One	4200.002	Four Thousand Two Hundred point Zero Zero Two
5	" Supply of HDPE TEE (EF) 160 mm X 110 mm X 160 mm "	nos	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	2500.001	Two Thousand Five Hundred point Zero Zero One	2500.001	Two Thousand Five Hundred point Zero Zero One
6	Supply of 110 mm dia HDPE 90° bend (EF)	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	15000.001	Fifteen Thousand point Zero Zero One	60000.004	Sixty Thousand point Zero Zero Four
7	Supplying and laying of single layer polythene sheet	sqm	9.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	15000.001	Fifteen Thousand point Zero Zero One	135000.009	One Lakh Thirty- Five Thousand point Zero Zero Nine
8	Supplying of Service connections Items of diameters 37 mm from distribution network composed	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	15020.001	Fifteen Thousand AND Twenty point Zero Zero One	60080.004	Sixty Thousand AND Eighty point Zero Zero Four

	of HDPE pipes.									
9	Supply, depositing and compaction of fine sand (FM 0.8) for backfilling up to required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	cum	111.690	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	300.001	Three Hundred point Zero Zero One	33507.112	Thirty-Three Thousand Five Hundred and Seven point One One Two
10	Supplying and spreading 1st class and picket bricks chips (LAA value not exceeding 40) including cost of bricks carrying, breaking into specified sizes including screening & specified sizes spreading uniformly on the road surface maintaining grade, camber and super elevation, etc. All complete as per direction of the E-I-C. 50mm downgraded	cum	2.280	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	3500.001	Three Thousand Five Hundred point Zero Zero One	7980.002	Seven Thousand Nine Hundred and Eighty point Zero Two
11	Supply of 37 mm Dia MS Gate Valve	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	3500.001	Three Thousand Five Hundred point Zero Zero One	14000.004	Fourteen Thousand point Zero Zero Four

12	Supply of Fire Brigade Connection 2 Way	nos	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	5000.001	Five Thousand point Zero Zero One	10000.002	Ten Thousand point Zero Zero Two
13	Supply of 37mm dia Hose pipe	m	120.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	900.001	Nine Hundred point Zero Zero One	108000.120	One Lakh Eight Thousand point One Two
14	Supply of 110 mm Dia MS Gate Valve	nos	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	china	9000.001	Nine Thousand point Zero Zero One	9000.001	Nine Thousand point Zero Zero One
								Grand Total:	733267.506	Seven Lakh Thirty-Three Thousand Two Hundred and Sixty-Seven point Five Zero Six

This Price and Delivery Schedule for Goods (Form e-PG2-2A) is Electronically Signed by Mr. Md Islam on behalf of NURJAHAN ENTERPRISE

NURJAHAN ENTERPRISE

Price and Completion Schedule for Related Services (Form e- PG2-2B)

Price and Completion Schedule for Related Services

Item No.	Description of Item	Measurement Unit	Quantity	Point of Completion	Completion Period (in days)	Country of Origin	Unit Price in Figure (BDT)	Unit Price in Words (BDT)	Total Price in Figure (BDT)	Total Price in Words (BDT)
1	"Mobilization and cleaning site before commencing actual physical work and during contract period and demobilization after completion of the works under contract to be accepted by the Engineer-in-charge. This work shall also covers clayey cleaning and clearing, cutting or filling, dressing the project area on and in the ground to an extent that all the events of works of the project can be executed smoothly in a working environment with a particular attention on safety and security in all respects, and to stockpile the end outcome to a place for disposal agreed by the Engineer-in-charge, where, payments are to be based on ground area determined by the Engineer-in-charge and be proportionate to the percentage progress of work under contract as a whole in all respects and approved by the Engineer-in-charge"	sqm	157.500	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	15750.158	Fifteen Thousand Seven Hundred and Fifty point One Five Eight
2	"Installation and laying of High Density Polyethylene (HDPE) water pipelines by Open Cut method in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for excavation in all kinds of soil, BFS/HBB/Bituminous road/Cement Concrete/Reinforced Cement Concrete road surface except rock to the full depth of trench required by the specifications, precautions necessary to avoid damage of underground utility services, (if any damage occurs, Contractor shall repair by his own cost) including removing the excavated earth & stacking the same to safe distance without any traffic obstacles, de-watering of the trench to keep dry condition at all times, including all necessary shoring, boxing, must be protected from any collapse of trench sides, transportation of pipes to site, cleaning, jointing and laying of the water pipes; as per specifications and direction of Engineering in charge"	m	204.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	20400.204	Twenty Thousand Four Hundred point Two Zero Four
3	"Extra-over item 1 for supplying and installing of HDPE (PN16, PE 100, SDR 11) fittings in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for transportation of fittings to site, cleaning, jointing and laying of the fittings as per specifications and direction of Engineering in charge. HDPE SLEEVE (EF) 110 MM (Only Laying Charge)"	nos	38.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	3800.038	Three Thousand Eight Hundred point Zero Three Eight
4	Extra-over item 1 for supplying and installing of HDPE (PN16, PE 100, SDR 11) fittings in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for transportation of fittings to site, cleaning, jointing and laying of the fittings as per specifications and direction of Engineering in charge. DI Dresser Coupler 200 MM (Only Laying Charge)	nos	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	10.001	Ten point Zero Zero One	20.002	Twenty point Zero Zero Two
5	"Extra-over item 1 for supplying and installing of HDPE (PN16, PE 100, SDR 11) fittings in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for transportation of fittings to site, cleaning, jointing and laying of the fittings as per specifications and direction of Engineering in charge. 110 mm dia HDPE 90° bend (EF)"	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	200.001	Two Hundred point Zero Zero One	800.004	Eight Hundred point Zero Zero Four

6	Bailing out of trapped water caused by inundation or rain, by pump from foundation trenches.	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	200.001	Two Hundred point Zero Zero One	800.004	Eight Hundred point Zero Zero Four
7	Extra-over item 1 for the procurement, carrying, supply, depositing and compaction of fine sand (FM 0.8) for bedding and surrounding the pipes up to required depth with proper ramming of 110mm layer as per specifications and direction of Engineering in charge and standard detail drawings for all pipelines.	cum	64.350	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	6435.064	Six Thousand Four Hundred and Thirty-Five point Zero Six Four
8	Extra-over item 1 for backfilling by excavated soil including depositing and compaction at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	cum	72.450	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	7245.072	Seven Thousand Two Hundred and Forty-Five point Zero Seven Two
9	Extra-over item 1 for installation including procurement, carrying, supply of Gate Valve/Non-return Valve/Pressure Sustaining Valve/Air Release Valve/ Washout Valve (BSPN 16) in accordance with the technical specification and the standard detailed drawings, of any diameter, specified below. The rate includes for transportation from plants to site, excavation, backfilling, dewatering, cleaning, jointing, laying and related fittings as per specifications and direction of Engineering in charge as per specifications and the standard detail drawing and direction of the Engineer in charge. 110 mm dia Gate valve (only Fitting Charge)	nos	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	100.001	One Hundred point Zero Zero One
10	Interconnection of water pipelines to any existing water supply networks, the rate includes for excavation, cutting, necessary plugging, dewatering, cleaning and unplugging, protection and repair of any existing structures. All works shall be done in accordance with Technical Specification and direction of Engineering in charge and Standard detail Drawings for the diameter of the existing water pipelines given below.	nos	2.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	100.001	One Hundred point Zero Zero One	200.002	Two Hundred point Zero Zero Two
11	Hire Charge of road surface Cutter Machine for Heavy surfaced Road (Mechanically). During construction/Rehabilitation of water to cut or dismantling the R.C.C, C.C Asphalt and Bituminous road surface by open cut Method using hard surface Mechanical cutting machine with necessary removal of dismantled materials. Providing temporary indication board, etc. Complete (As per item no 1 both site).	m	408.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	50.001	Fifty point Zero Zero One	20400.408	Twenty Thousand Four Hundred point Four Zero Eight
12	Reconstruction and repairing of other utilities services Telephone/Gas/Electricity/Sewer/surface & underground drains/storms sewer pit or any other system in the pipe alignment), includes all necessary materials, cables, replacement, reinstallation, repairing of broken service manhole, sewer pit including supply of all types of cables, pipes, fittings, course & fine aggregates, bricks, cement and any other works in accordance with Technical Specification and direction of Engineering in charge, each unit includes total safety, repair, replacement of other utilities for each 100 meter pipelines alignment, all mentioned cost will be paid by Contractor.	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	20.001	Twenty point Zero Zero One	80.004	Eighty point Zero Zero Four
13	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II / B-M)	cum	2.340	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	20.011	Twenty point Zero One One	46.826	Forty-Six point Eight Two Six
14	Hiring charge for supply and sqm installation of MS sheets (1800x900x18mm) charge.	sqm	9.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	2.001	Two point Zero Zero One	18.009	Eighteen point Zero Zero Nine

15	The excavation of trial holes (1.2 m x 0.6 m x 1.5m) in accordance with the technical specification. and Standard detail drawings and direction of Engineer in charge.	nos	4.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	20.001	Twenty point Zero Zero One	80.004	Eighty point Zero Zero Four
16	Procurement, carrying, supplying of all necessary materials and Construction of Gate valves surface box in the network including supports and all piping, fittings and other equipment in accordance with the specification and standard detail drawings	nos	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	20.001	Twenty point Zero Zero One	20.001	Twenty point Zero Zero One
17	Supply of Goods Loding/Unlodng and Site Clening Work	item	1.000	saidabad water treatment plant, Dhalpur, Dhaka.	180	BD	2.001	Two point Zero Zero One	2.001	Two point Zero Zero One
								Grand Total:	76197.802	Seventy-Six Thousand One Hundred and Ninety-Seven point Eight Zero Two

This Price and Completion Schedule for Related Services (Form e- PG2-2B) is Electronically Signed by Mr. Md Islam on behalf of NURJAHAN ENTERPRISE