Office of the Executive Engineer
PSTP Division, Dhaka WASA.

Subject: Supply of barbed wire fencing, emulsion paint, etc. and related services North-East side at Mohammadbagh water pump.

A. Price Schedule for Goods (Form e-PG2-3A)

SL No	Description of Items (Goods & related services)	Unit	Quantity	Rate	Amount
1	Supplying, fitting and fixing 12 BWG barbed wire fencing in a circular shape of 600 mm dia and 100 mm pitch fitted with MS rod casing (made by 8 nos. 10 mm dia plain bar in a circular pattern and placed at equal interval), 38 mm x 38 mm x 6 mm M.S. angle post (300 mm embedded in RCC or in brick work with a cement concrete base of 75 mm x 75 mmx 300 mm) and 600 mm vertical and 450 mm inclined placed@ 3.0 m c/c including straightening, binding the joints with18 BWG wire, making holes in the angle etc. including supplyof all necessary materials complete in all respect and accepted by the Engineer-in-charge. (Rate is excluding the cost of Painting).	meter	100.00	2553.00	255300.00
2	1st class/Picked jhama standard bricks	each	5200.00	13.00	67600.00
3	Ordinary Portland Cement, BDS-EN - 197-1-CEM-I ,52.5N, 50 kg bag	Per Bag	185.00	405.00	74925.00
4	Supply of sand as per sample	Cft	960.00	19.00	18240.00
5	Standard exterior emulsion paint	per litre	139.00	430.00	59770.00
6	Sealer for exterior emulsion paint	per litre	185.00	195.00	36075.00
7	Ready-mix putty (exterior)	per kg	582.00	64.00	37248.00
				Sub Total Taka (A)	549158.00

B. Price Schedule for Related Services (Form e-PG2-3B)

1	Head mason / Mosaic head mistry	per day	45.00	800.00	36000.00
2	Mason / Mosaic mistry	per day	128.00	700.00	89600.00
3	Ordinary labour	per day	178.00	550.00	97900.00
4	Painter	per day	139.00	700.00	97300.00
5	Helper	per day	139.00	550.00	76450.00
				Sub Total Taka (B)	397250.00
				Grand Total Taka (A+B)	946451.00

Taka (in words): Nine Lakh Forty Six Thousand Four Hundred Fifty One Point Zero Zero Only.

30/04/26
Sub-Assistant Engineer
PSTP Division,Dhaka WASA.

10.5.2026
Sub-Divisional Engineer
PSTP Division,Dhaka WASA.

Executive Engineer
PSTP Division,Dhaka WASA.