

Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works: Removal of dirty water from the house no. Ta-55 to Ta-69/1 in the lane in front of Boishakhi sarani road, Badda (DMA-807) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	160 mm dia HDPE Pipe	3.00	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Sleeve E.F	2.00	Nos	5500.000	11,000.000	
3	Approved Rate	Earth work in Excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead $(2*4*2.75*1.68)=36.740$ cum	36.960	P/Cum	168.001	6209.317	
4	Approved Rate	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters. $(2*4*2.50*1.67)=33.400/2=16.700$ cum	16.700	P/Cum	578.001	9652.617	
5	Approved Rate	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutcha road surface. $(2*4*2.50*1.67)=33.400/2=16.700$ cum	16.700	P/Cum	154.001	2571.817	
6	Approved Rate	B) Removal of excavated earth/debris etc $(2*4*2.25*1.67)=30.06$ cum $/2=15.03$ cum	15.030	P/Cum	288.001	4,328.655	
7	Approved Rate	Mechanics Charge	3	P/Person	1000.000	3000.000	
8	Approved Rate	Skilled Technician	7	P/Person	1000.000	7000.000	
9	Approved Rate	Hire charge of de-watering pump	2	P/Day	2000.000	4000.000	
Total Tk.=						47762.405	

In words: Forty Seven Thousand Seven Hundred Sixty Two point Four Zero Five Taka Only.


20/09/2026
মোঃ মাসুদুল করিম
উপ. সহকারী প্রকৌশলী
মডস জোন-০৮
ঢাকা ওয়াসা।


20.09.26
মোঃ মোস্তফা
সহকারী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা


20/09/2026
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।