

M/s Zaman Traders**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item no.	Group	Item Code (if any)	Description of Item	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	Select 'YES' to see the Grand Total
1	A	N/A	Carrying the pump set including other materials ? column pipes, shaft, bend, motor discharge head, clamp, tools etc. complete from central store/F.M Divn. to P/S and returning of the rest by providing vehicles , drivers, fuell all complete.	Per trip	50.000	2025.001	Two Thousand And Twenty-Five Point Zero Zero One	101250.050	One Lakh One Thousand Two Hundred And Fifty Point Zero Five	Yes
2	A	N/A	Providing Tripod & chain pulley including carrying, setting, dismantling and returning all complete.	Per set	50.000	1793.001	One Thousand Seven Hundred And Ninety-Three Point Zero Zero One	89650.050	Eighty-Nine Thousand Six Hundred And Fifty Point Zero Five	Yes
3	A	N/A	Withdrawal of submersible pump, cable, bend etc. all complete	Per set	50.000	978.001	Nine Hundred And Seventy-Eight Point Zero Zero One	48900.050	Forty-Eight Thousand Nine Hundred Point Zero Five	Yes
4	A	N/A	Withdrawn of flange ended column pipe (39 nos per well on avererage Total=50x39=1950 Nos), pump cable, cable guard, bend, bubber gasket, base plate etc.	Each	1950.000	247.001	Two Hundred And Forty-Seven Point Zero Zero One	481651.950	Four Lakh Eighty-One Thousand Six Hundred And Fifty-One Point Nine Five	Yes
5	A	N/A	Collecting of DTW data such as static water level (SWL), total fixture length clear, continuity test of sub-pump cable & motor.	per job	50.000	350.001	Three Hundred And Fifty Point Zero Zero One	17500.050	Seventeen Thousand Five Hundred Point Zero Five	Yes
6	A	N/A	Installation of sub-pump, motor, cable,	per set	50.000	943.001	Nine Hundred	47150.050	Forty-Seven	Yes

			bend etc. all complete				And Forty- Three Point Zero Zero One		Thousand One Hundred And Fifty Point Zero Five	
7	A	N/A	Installaion of flange ended column pipe (39 nos per well on average Total=39x50=1950 Nos), pump cable, cable guard, bend, rubber gasket, base plate etc.	Each	1950.000	268.001	Two Hundred And Sixty- Eight Point Zero Zero One	522601.950	Five Lakh Twenty-Two Thousand Six Hundred And One Point Nine Five	Yes
8	A	N/A	MS Tripod setting to ensure the proper working environment such as sand filling for etc.	per job	40.000	2000.001	Two Thousand Point Zero Zero One	80000.040	Eighty Thousand Point Zero Four	Yes
9	A	N/A	Disconnection, reconnection, cleaning of stater/VFD & all other electrical connections, setting and adjusting all electrical parameter according to new install pump motor set and temperature controller under supervision of a ABC licence holder supervisor by skilled electrician.	per job	50.000	1874.001	One Thousand Eight Hundred And Seventy- Four Point Zero Zero One	93700.050	Ninety- Three Thousand Seven Hundred Point Zero Five	Yes
							Grand Total:	1482404.240	Fourteen Lakh Eighty-Two Thousand Four Hundred And Four Point Two Four	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md. Rashed Kabir on behalf of M/s Zaman Traders

M/s Zaman Traders

Tenderer's Quoted Price

Tenderer's Quoted Price			
Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
1482404.240	-5.000	1408284.028	Fourteen Lakh Eight Thousand Two Hundred And Eighty-Four Point Zero Two Eight
	Grand Total:	1408284.028	Fourteen Lakh Eight Thousand Two Hundred And Eighty-Four Point Zero Two Eight

This Tenderer's Quoted Price is Electronically Signed by Mr. Md. Rashed Kabir on behalf of M/s Zaman Traders