


**Office Of the Executive Engineer
Pagla Sewage Treatment Plant, Dhaka WASA**

Name of the work: Cleaning of inlet and outlet chamber with related works of Dholaikhal SLS under PSTP.

Sl. No.	Description of items(Works)	Qty	Unit	Unit Rate (Tk.)	Total Amount
1	Cleaning inlet and delivery chamber, sump well, screen box, gate box, catch pits etc. cleaning the sludges and any other foreign materials manually by using labourer or by any other means from the existing base of the line without making any damage to the structure including supply of all necessary equipments and materials such as mask, safety helmet, hand gloves, Oxygen cylinder, compressor, diver etc. if necessary to ensure the proper cleaning and safety of labourer as per direction of the engineer-in -charge.	64.33	cum	289.000	18,590.879
2	Removal of Pipe line and Brick sewer sludge from the cleaning site up to the nearest D.C.C. dumping yard carrying loading unloading etc. complete as per direction of the Engineer-in-charge.	57.90	cum	326.000	18,873.923
3	Bailing out water by 1 cusec diesel operated pump including hire charge of pump, fuel, operator, spares and maintenance etc. all complete and accepted by by the Engineer-in-charge.	18.00	hr	677.000	12,186.000
Grand Total Tk.=					49,650.802
Taka In Words: Forty Nine Thousand Six Hundred Fifty Point Eight Zero Two.					


22/10/25
Md. Mamunur Rahman
Sub-Assistant Engineer
PSTP Division, Dhaka WASA


22.10.2025
Md. Saiful Islam
Sub-Divisional Engineer
PSTP Division, Dhaka WASA


22/10/25
Syed Shihabur Rahman
Executive Engineer
PSTP Division, Dhaka WASA