

Dhaka Water Supply and Sewerage Authority

Office of the Executive Engineer

Meter Division

4/4, Shegunbagicha, Dhaka

Name of work: Repair of CI Sheet (Damage Portion), False Ceiling with necessary maintenance works at Meter Division, Segunbagicha, Dhaka.

Sl. No.	Basis of Rates	Description of Item	Quantity		Rate		Amount (Tk)
1	2	3	4		5		6
1	15.1	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, sca	60.669	sqm	316.001	p/sqm	19,171.465
2	10.21	Supply and installation of 0.457 mm thick corrugated galvanized iron sheet (Bangladesh made) having min weight 63-65 kg per bundle (2'-6" width, 70 - 72 ft long) fitted and fixed on M.S. sections with 'J' hook or wooden purlin with screws, limpet washers and putty etc. (up to level-4) all complete and accepted by the Engineer-in-charge.	239.063	sqm	578.001	P/sqm	138,178.653
3	18.2.1.2	Supplying, fitting and fixing 12 mm thick burma teak (BT) veneered board/ ply board/ particle board in walling with best quality and well seasoned garjan wood frame of section of 50 mm x 25 mm at 600 mm x 600 mm in grid, including grove where necessary, fitted and fixed to wall by plugs, nails, screws etc. maintaining leveled and finished exposed faces including making holes in wall and mending good the damages, if any during execution of the work, including the provisions of lighting arrangement, also including cost and carriage of all materials, electricity, accessories, labour for installation, scaffolding, screws, nails etc. All complete as per design, approved sample and accepted by the Engineer-in-charge. All sizes of wood are finished. All Garjan wood frames must be protected from termites, cockroach and other insects. Measurement will be taken as per finished surface area. The brick/ RCC surface shall be dry and damp-proof. (Rate is excluding cost of polish/ paint etc. of any type)	53.532	sqm	3,098.001	P/sqm	165,842.190



ওবায়দুর রহমান
উপ-সহকারী প্রকৌশলী
মিটার বিভাগ, ঢাকা ওয়াসা



মঃ মাহবুব হাসান
নির্বাহী প্রকৌশলী
মিটার বিভাগ
ঢাকা ওয়াসা

4	16.11	Approved best quality and colour synthetic polyvinyl distemper delivered from authorized local agent of the manufacturer in a sealed container, applying to wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying 1 coat of interior sealer of specified brand on prepared surface; then applying 1 coat of interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of synthetic polyvinyl distemper spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	649.723	sqm	213.001	P/sqm	138,391.649
5	16.3.2	Premium synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property; using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in two coats over single coat anti-corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	87.825	sqm	238.001	p/sqm	20,902.438
6	26.52	Supplying, fitting and fixing of best quality faucets etc. complete approved and accepted by the Engineer- in- charge.					
	26.52.1	12 mm CP bib cock	2.00	nos	1,172.001	Each	2,344.002
7	M/R	Electrical line & fittings	1.000	nos	5,000.001	Each	5,000.001
8	M/R	Water line & fittings	1.000	nos	5,000.001	Each	5,000.001
Total (Tk)							494,830.399
Say Total TK.							494,830

In Word: Four Lakh Ninety Four Thousand Eight Hundred Thirty Taka Only


 ১৭.০৪.২০২৩
 ওবায়দুর রহমান
 উপ-সহকারী প্রকৌশলী
 মিটার বিভাগ, ঢাকা ওয়াসা


 ১৭/০৭/২৩
 মাহবুব হাসান
 হী প্রকৌশলী
 টার বিভাগ
 ঢাকা ওয়াসা