

M/S SHARIF TRADERS**Priced Bill of Quantities (BOQ)****Unit Rate Basis**

Estimate by the Procuring Entity

Item no.	Group	Item Code (if any)	Description of Item	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	Select 'YES' to see the Grand Total
1	N/A	N/A	Extra-over item 1 for completion temporary re-instatement of the existing surfaced road in accordance with the technical specification and standard detail drawings, for all sewer pipe diameter . Concrete Asphalt road surface	P/sqm	51.150	64.001	Sixty-Four Point Zero Zero One	3273.651	Three Thousand Two Hundred And Seventy-Three Point Six Five One	Yes
2	N/A	N/A	Earthwork in excavation of tank of any dimension in all kinds of soil including cutting up to required depth including bailing out water and throwing on the embankment, breaking clods, ramming and leveling, dressing in 225 mm layer with maintaining the side slopes and level of both tank and the embankment as per design and accepted by the Engineerin-charge.For initial lead of 30 m and lift of 1.5 m	P/cum	61.380	185.000	One Hundred And Eighty-Five	11355.300	Eleven Thousand Three Hundred And Fifty-Five Point Three	Yes
3	N/A	N/A	Brick works of width one brick or one and a half brick length of first class bricks with cement sand (F.M. 1:2) mortar (1:6) in superstructure including raking out joints, filling the interstices with mortar, cleaning and soaking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7	P/cum	14.960	6443.000	Six Thousand Four Hundred And Forty-Three	96387.280	Ninety-Six Thousand Three Hundred And Eighty-Seven Point Two Eight	Yes

			days etc. all complete (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) and accepted by the Engineer-in-charge. (Cement: CEM-II/A-M) In ground floor							
4	N/A	N/A	Mass concrete (1:2:4) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by Engineer-in-charge. (Cement: CEM-II/A-M) Mass concrete in floor (1:2:4) with brick chips and local sand of F.M. 1.2.	P/cum	10.660	7575.000	Seven Thousand Five Hundred And Seventy-Five	80749.500	Eighty Thousand Seven Hundred And Forty-Nine Point Five	Yes
5	N/A	N/A	"Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to dado with cement (1:4) up to 150 mm including washing of sand, finishing the edges and corners and curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-incharge. (Cement: CEM-II/A-M) ground floor."	P/Sqm	40.680	295.000	Two Hundred And Ninety-Five	12000.600	Twelve Thousand Point Six	Yes
6	N/A	N/A	"Back filling the trenches with sand (F.M 0.8) in 150 mm layer, compaction of each layer up to finished level as per standard practice and accepted by the Engineer-in-charge."	P/Cum	46.550	683.000	Six Hundred And Eighty-Three	31793.650	Thirty-One Thousand Seven Hundred And Ninety-Three Point Six Five	Yes
7	N/A	N/A	"Removal of sewer sludge from the cleaning site by Dump	Trip	9.000	3500.000	Three Thousand	31500.000	Thirty-One Thousand	Yes

			Truck including carrying, loading, unloading etc. complete as per direction of the Engineer-in-charge. Each Gorup 1280 bag Each trip 150 Bag 1280/150= 8.53 trip"				Five Hundred		Five Hundred	
8	N/A	N/A	"Hiring of Van with Van Puller for stacking lifted sludge from sewer line and sewer pit/manhole. "	Day	15.000	1200.000	One Thousand Two Hundred	18000.000	Eighteen Thousand	Yes
9	N/A	N/A	Supply of Plastic bag for keeping lifted sludge from sewer line and sewer pit/manhole.	Each	1280.000	15.000	Fifteen	19200.000	Nineteen Thousand Two Hundred	Yes
10	N/A	N/A	Daily labor for demolition of rock & cleaning of rough tree, wastage materials etc and dressing of full compound..all complete and accepted by the Engineer	Person	128.000	1200.000	One Thousand Two Hundred	153600.000	One Lakh Fifty-Three Thousand Six Hundred	Yes
11	N/A	N/A	"Shore protection work during excavation in foundation trenches up to 1.5 m depth to protect loss due to damage of property by palisading accepted by the Engineer-in-charge. [The rate is including the cost of vertical post]"	P/sqm	64.960	609.001	Six Hundred And Nine Point Zero Zero One	39560.704	Thirty-Nine Thousand Five Hundred And Sixty Point Seven Zero Four	Yes
							Grand Total:	497420.685	Four Lakh Ninety-Seven Thousand Four Hundred And Twenty Point Six Eight Five	

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Md Uddin on behalf of M/S SHARIF TRADERS