


Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.

Name of Works : Repairing of HDPE Water Line Leakage & Removal dirty Water In Road no-19 & 08, Block no- G & I, Bashundhara (DMA-801) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	110 mm dia HDPE Pipe	3.00	P/M			Supply by Sub store
2	Approved Rate	110 mm dia HDPE Sleeve E.F	4.00	Nos	2600.000	10,400.000	
3	Approved Rate	Earth work in Excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead(2*4*2.75*1.68)= 36.960 cum	36.960	Cum	168.001	6209.317	
4	Approved Rate	Repairing of water line leakage for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.(2*4*2.50*1.68)= 33.600)/2=16.800 cum	16.800	Cum	578.001	9710.417	
5	Approved Rate	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface(2*4*2.10* 1.67) =28.05cum)/2= 14.025 cum	14.025	Cum	154.001	2159.864	
6	Approved Rate	B) Removal of excavated earth/debris etc(2*4*2.25*1.67) =30.060cum)/2 = 15.030 cum	15.030	Cum	288.001	4,328.655	
7	Approved Rate	Mechanics Charge	5	P/Person	1000.000	5000.000	
8	Approved Rate	Skilled Technician	6	P/Person	1000.000	6000.000	
9	Approved Rate	Hire charge of de-watering pump	2	P/Day	2000.000	4000.000	
Total Tk.=						47808.253	

In words: Forty Seven Thousand Eight Hundred Eight point Two Five Three Taka Only.


17/08/26
মোঃ নূরুল হোসেন
উপ-সহকারী প্রকৌশলী
মডস জোন-০৮
ঢাকা ওয়াশা।


17/08/26
মোঃ গোলাম মোস্তফা
উপ-বিভাগীয় প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াশা।


17/08/26
মোঃ নূরুল করিম
নির্বাহী প্রকৌশলী
মডস জোন
ঢাকা ওয়াশা।