

**Office of the Executive Engineer
MODS Zone-10, Dhaka WASA**

Cost of Estimate : Leakage repair work on Various roads in Uttara Sector-16 , Block - A & B Area DMA-1012 under Mods Zone-10, Dhaka WASA.

SL No	Rate Schedule	Description of the item	Unit	Quantity	Rate(Tk.)	Amount (Tk.)
1	pwd 02.1.2	Earthwork in excavation in foundation trenches up to 1.5 m depth and maximum 10 m lead	cum	22.5	168.09	3782.03
2	pwd 02.10.1	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 to FM 0.8	cum	10.9	1088.00	11859.20
3	WASA-7	Back filling by excavated granular soil	cum	11.60	134.00	1554.40
4	Market rate fixed by WASA	Labour	P/Person	10	800.00	8000.00
5	Market rate fixed by WASA	Skilled technician/Mechanics for HDPE pipe cutting, fitting and operating cutting disk.	P/Person	2	1000.00	2000.00
6	Pre-Approved Rate	Hire Charge of electrofusion machine to joint sleeve in the excavation. all complete as per direction of the E/C.	P/day	2	1500.00	3000.00
7	Pre-Approved Rate	Hire charge of de-watering Pump	Nos	4	2000.00	8000.00
8	Pre-Approved Rate	Generator Mechine Hire Charge	P/day	2	2,000.00	4,000.00
9	Market rate	Safety Barriers Bamboo, Wooden, Planked Rope, G.I Wire for temporary shoring and boxing to the side of the excavation to maintain a safe working environment for anf depths.	LS	LS	7000.00	7000.00
Total						49195.63

In Word : Forty Nine Thousand One Hundred Ninety Five Point Six Three Tk only.


মোস্তাফিজ বিদ্রাহ আলমগীর
উপ-সহকারী প্রকৌশলী
মডস জোন-১০, ঢাকা ওয়াসা।


Md. Chandra Mohanayok
Assistant Engineer
MODS Zone-10
Dhaka WASA.


Md. Asaduzzaman
Executive Engineer
MODS Zone-10, Dhaka WASA.