

M/S MAA BASAR DUA ENTERPRISE

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Sewer	1/1	Excavation in all materials except rock for the construction of main sewer manholes to the full depth and maximum dimensions required by the Specification in the various depth ranges give below, all in accordance with the Technical Specification and Standard detail Drawings. The rate include for all necessary dewatering to maintain the excavation in a dry condition at all times; preparation of the bottom of the excavation. (Cost of excess excavated earth would be deducted as per deptt. materials rate.)	m3	104.060	149.001	One Hundred and Forty-Nine point Zero Zero One	15505.044	Fifteen Thousand Five Hundred and Five point Zero Four Four	I have seen
2	Sewer	5/b	Placing of Mass concrete for the base of service pit & Benching to manhole and service pit, including the supply of all materials all in accordance with the technical specification and standard drawings. a) Mass concrete (1:2:4) for cover slab & benching of M.H& pit.	m3	0.910	5654.001	Five Thousand Six Hundred and Fifty-Four point Zero Zero One	5145.141	Five Thousand One Hundred and Forty-Five point One Four One	I have seen
3	Sewer	6	Erection of Brickwork for the walls of manhole and service pit, at any req. depth, all in accordance with the technical specification and standard details drawings. the rate to include for the supply of first class bricks, the preparation of sand cement mortar(1:4) including the supply of all materials and flush pointing to the face of the brickwork wall.	m3	16.290	4819.001	Four Thousand Eight Hundred and Nineteen point Zero Zero One	78501.526	Seventy-Eight Thousand Five Hundred and One point Five Two Six	I have seen
4	Sewer	7	Extra over item 4/1 for the provision of sand cement plaster(1:4) to the external faces of manhole and services pit in place of the flush pointing finish, all in accordance with the technical specification and standard Details. The rate to include for the supply of all materials.	m2	65.160	179.001	One Hundred and Seventy-Nine point Zero Zero One	11663.705	Eleven Thousand Six Hundred and Sixty-Three point Seven Zero Five	I have seen
5	Sewer	8/B	Supply of Fit cast Iron Manhole Cover to manhole and service pits for the clear access as given below, all in accordance with the Technical Specification and the Standard Detail Drawings. The rate to include for Bitumen painting of the cover and setting in Class A Mass Concrete (with Cement) including the supply of all materials.(Excluding cost of Cement) b)550 mm. Diameter for main Sewer Manholes	Nr	10.000	801.001	Eight Hundred and One point Zero Zero One	8010.010	Eight Thousand AND Ten point Zero One	I have seen
6	Sewer	9	Supply and Fitting Cast Iron Step-Irons to manholes and service pits, all in accordance with the Technical	Nr	40.000	854.999	Eight Hundred and Fifty-Four	34199.960	Thirty-Four Thousand	I have seen

			supply of materials) and building in to the chamber walls as brickwork erection proceeds.				Nine Nine Nine		Ninety-Nine point Nine Six	
7	Sewer	11	Provision of Bituminous Coating to the external faces of Manholes and service pits at all depths, in accordance with the Technical Specification. To include for the supply of all materials.	m2	65.160	105.001	One Hundred and Five point Zero Zero One	6841.865	Six Thousand Eight Hundred and Forty-One point Eight Six Five	I have seen
8	Sewer	11/1	Extra-over item 1 for the supply and placing of saturated river sand / earth backfield for all required trench depths in accordance with the technical specification and standard detail drawings, for all sewer pipe diameters. a) Back filling by saturated river sand (at any depth)	m3	66.430	503.001	Five Hundred and Three point Zero Zero One	33414.356	Thirty-Three Thousand Four Hundred and Fourteen point Three Five Six	I have seen
9	Sewer	16	Provision for bailing out of all kinds of sewage and sludge from existing sewer line for making dry and working arrangement in downstream of working area with all leads & lifts of pumps or any other means etc. all complete as per direction of the Engineer in charge .	day	10.000	1862.001	One Thousand Eight Hundred and Sixty-Two point Zero Zero One	18620.010	Eighteen Thousand Six Hundred and Twenty point Zero One	I have seen
10	Sewer	18	Removal of Excavated earth and clean the site for a smooth traffic movement during execution of the works and as per direction of the Engineer-in charge..	m3	66.430	287.999	Two Hundred and Eighty-Seven point Nine Nine Nine	19131.774	Nineteen Thousand One Hundred and Thirty-One point Seven Seven Four	I have seen
11	Sewer	19/a	Demolition of the existing RCC/CC/Brick Sewer deck slab/foundation/wall/railing/abutment/beam etc. with soling under RCC/CC in bed, without disturbing the foundation soil and dumping the materials to a safe place as per direction of the Engineer. a)RCC/CC work	m3	1.090	1251.001	One Thousand Two Hundred and Fifty-One point Zero Zero One	1363.591	One Thousand Three Hundred and Sixty-Three point Five Nine One	I have seen
12	Sewer	19/b	Demolition of the existing RCC/CC/Brick Sewer deck slab/foundation/wall/railing/abutment/beam etc. with soling under RCC/CC in bed, without disturbing the foundation soil and dumping the materials to a safe place as per direction of the Engineer. b) Brick work (sewer/wall)	m3	17.810	668.999	Six Hundred and Sixty-Eight point Nine Nine Nine	11914.872	Eleven Thousand Nine Hundred and Fourteen point Eight Seven Two	I have seen
13	Sewer	MP	Site Cleaning, Providing Safety Measures	LS	1.000	2999.878	Two Thousand Nine Hundred and Ninety-Nine point Eight Seven Eight	2999.878	Two Thousand Nine Hundred and Ninety-Nine point Eight Seven Eight	I have seen
Grand								247311.732	Two Lakh	

5 PM

View Form

Three Hundred and Eleven point Seven Three Two

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mrs. Salma Sultana on behalf of M/S MAA BABAR DUA ENTERPRISE

M/S MAA BABAR DUA ENTERPRISE**Tenderer's Quoted Price**

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
247311.732	-5.000	234946.145	Two Lakh Thirty-Four Thousand Nine Hundred and Forty-Six point One Four Five
	Grand Total:	234946.145	Two Lakh Thirty-Four Thousand Nine Hundred and Forty-Six point One Four Five

This Tenderer's Quoted Price is Electronically Signed by Mrs. Salma Sultana on behalf of M/S MAA BABAR DUA ENTERPRISE