

M/S MAA BABAR DUA ENTERPRISE

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	Water Line	1/1.d	uPVC Pipe(PN-10) (ISO4422-2)1996 Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement Annex --Section?) in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. 160 mm dia	p/m	18.200	1013.151	One Thousand AND Thirteen point One Five One	18439.348	Eighteen Thousand Four Hundred and Thirty-Nine point Three Four Eight	I have seen
2	Water Line	1/1.e	uPVC Pipe(PN-10) (ISO4422-2)1996 Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement Annex --Section?) in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. 225mm dia	p/m	15.600	1938.901	One Thousand Nine Hundred and Thirty-Eight point Nine Zero One	30246.856	Thirty Thousand Two Hundred and Forty-Six point Eight Five Six	I have seen
3	Water Line	1/1.f	uPVC Pipe(PN-10) (ISO4422-2)1996 Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement Annex --Section?) in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. 250-280mm dia	p/m	6.500	2990.001	Two Thousand Nine Hundred and Ninety point Zero Zero One	19435.007	Nineteen Thousand Four Hundred and Thirty-Five point Zero Zero Seven	I have seen

			Installation and laying of (uPVC) Unplasticized polyvinyl chloride/DI / PE /MS water pipelines (including supply of materials, fittings, Equipment described in schedule of requirement Annex --Section?) in accordance with the technical specification and the standard detailed drawings, of any diameter specified below. The rate includes for excavations as per specifications and direction of Engineering in charge 315mm dia				Eight Hundred and Nine point Nine Five One		Thousand Seven Hundred and Seventeen point Six One Eight	seen
5	Water Line	4/2.b	CI Dresser Coupling Extra-over item 1 for the supply (including supply of fittings described in schedule of requirement Annex-----) and installation following adopters for jointing components of pipelines, diameter given below, as per specifications and direction of Engineering in charge and the standard details drawings 150 mm dia Dresser Coupling in/c nut-bolts.	Nr	28.000	1411.051	One Thousand Four Hundred and Eleven point Zero Five One	39509.428	Thirty-Nine Thousand Five Hundred and Nine point Four Two Eight	I have seen
6	Water Line	4/2.d	CI Dresser Coupling Extra-over item 1 for the supply (including supply of fittings described in schedule of requirement Annex-----) and installation following adopters for jointing components of pipelines, diameter given below, as per specifications and direction of Engineering in charge and the standard detail drawings 225 mm dia Dresser Coupling in/c nut-bolts	Nr	24.000	1667.501	One Thousand Six Hundred and Sixty-Seven point Five Zero One	40020.024	Forty Thousand AND Twenty point Zero Two Four	I have seen
7	Water Line	4/2.e	Extra-over item 1 for the supply (including supply of fittings described in schedule of requirement Annex-----) and installation following adopters for jointing components of pipelines, diameter given below, as per specifications and direction of Engineering in charge and the standard detail drawings. 250 mm dia Dresser Coupling in/c nut-bolts	Nr	10.000	2357.501	Two Thousand Three Hundred and Fifty-Seven point Five Zero One	23575.010	Twenty-Three Thousand Five Hundred and Seventy-Five point Zero One	I have seen
8	Water Line	4/2.f	Extra-over item 1 for the supply (including supply of fittings described in schedule of requirement Annex-----) and installation following adopters for	Nr	8.000	3018.751	Three Thousand AND Eighteen point Seven	24150.008	Twenty-Four Thousand One Hundred and Fifty	I have seen

			below, as per specifications and direction of Engineering in charge and the standard detail drawings. 300 mm dia Dresser Coupling in/c nut-bolts							
9	Water Line	6/a.	Extra-over item 1 for the supply, depositing and compaction of fine sand (FM 0.8) bedding, surrounding and above pipes up to required depth with proper ramming of 150mm layer as per specifications and direction of Engineering in charge and standard detail drawings for all pipelines. a)Bedding and surrounding by River Saturated Sand (F.M 0.8).	m3	7.843	578.451	Five Hundred and Seventy-Eight point Four Five One	4536.791	Four Thousand Five Hundred and Thirty-Six point Seven Nine One	I have seen
10	Water Line	6/b.	b)Extra-over item 1 for the supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters. .	m3	86.275	578.451	Five Hundred and Seventy-Eight point Four Five One	49905.860	Forty-Nine Thousand Nine Hundred and Five point Eight Six	I have seen
11	Water Line	7	Back filling by excavated granular soil including depositing and compaction at all required depth in accordance with the technical specification by excavated soil for kutchra road surface	m3	31.059	154.101	One Hundred and Fifty-Four point One Zero One	4786.223	Four Thousand Seven Hundred and Eighty-Six point Two Two Three	I have seen
12	Water Line	8/a.	Extra over item 1 for completing temporary reinstatement of rigid and flexible paved road by compacted sand (FM 1.2) of 75 mm thick and one layer brick soling by full burned 1st class bricks of appropriate size (excavated bricks of proper sizes and quality is allowed to use) of the existing surfaced road in accordance with the technical specification and direction of Engineering in charge, and standard detail drawing for all water pipeline of any diameters for the type of road Surface given below. Asphalt/concrete road surface	m2	52.288	73.601	Seventy-Three point Six Zero One	3848.449	Three Thousand Eight Hundred and Forty-Eight point Four Four Nine	I have seen
13	Water Line	16/1	Shifting and connection of existing Service Lines to improved systems for all depths, diameters, length up to meter chambers at consumers premises. The	Each	16.000	1398.401	One Thousand Three Hundred and Ninety-	22374.416	Twenty-Two Thousand Three Hundred and	I have seen

			Pipe , excavation, PVC clamp saddles or CI clamps, quality fittings, valves, appropriate drilling system for making holes in pipes, backfilling with sand (FM 0.8), plugging, de-watering, cleaning, unplugging, fitting fixing of float valve / check valve at the end of service line(in the reservoirs), shifting or change of service meter.All works shall be done in accordance with Technical Specification, direction of Engineering in charge and approved drawings. 1)DN 20 to DN 25mm dia					Four Zero One		Four One Six	
14	Water Line	9	Extra-over item 1 for the excavation and removal of soft soil (on written permission of E/C) from the trench bottom beyond allowable depth and back fill of this by supplying, depositing and compaction in 150 mm layer of fine sand (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge.	m3	94.118	331.201		Three Hundred and Thirty-One point Two Zero One	31171.976	Thirty-One Thousand One Hundred and Seventy-One point Nine Seven Six	I have seen
15	Water Line	19	Hiring charge for supply and installation of MS sheets (1800x900x18mm) over the trench / road surface for a smooth traffic movement during the execution of works in accordance with Technical Specification and direction of Engineering in charge.	m2	8.100	445.051		Four Hundred and Forty-Five point Zero Five One	3604.913	Three Thousand Six Hundred and Four point Nine One Three	I have seen
16	Water Line	20	Hire charge of de-watering Pump : Bailing out of all water from pipe line trench with supply of de-watering pump required size including supplying of fuel lubricants and all other required accessories & manpower to keep the trench in a dry condition at all times etc. all completed as per direction of the E/C.	day	15.000	2141.301		Two Thousand One Hundred and Forty-One point Three Zero One	32119.515	Thirty-Two Thousand One Hundred and Nineteen point Five One Five	I have seen
17	Water Line	MP	Site Cleaning and providing safety measures.	LS	1.000	8999.579		Eight Thousand Nine Hundred and Ninety-Nine point Five Seven Nine	8999.579	Eight Thousand Nine Hundred and Ninety-Nine point Five Seven Nine	I have seen
Grand Total:									386441.021	Three Lakh Eighty-Six	

M/S MAA BABAR DUA ENTERPRISE**Tenderer's Quoted Price**

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
386441.021	-5.000	367118.970	Three Lakh Sixty-Seven Thousand One Hundred and Eighteen point Nine Seven
	Grand Total:	367118.970	Three Lakh Sixty-Seven Thousand One Hundred and Eighteen point Nine Seven

This Tenderer's Quoted Price is Electronically Signed by Mrs. Salma Sultana on behalf of M/S MAA BABAR DUA ENTERPRISE