

M/s. Nasima Enterprise

Priced Bill of Quantities (BOQ)

Unit Rate Basis

Estimate by the Procuring Entity

Item No.	Group	Item Code (If any)	Description of Items of Works (specifications preferably built-in)	Unit	Quantity	Unit rates or prices (in figures) (BDT)	Unit rates or prices (in words) (BDT)	Amount (in figure) (BDT)	Amount (in words) (BDT)	I have seen
1	--	N/A	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge. Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.5 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	Cum	24.000	1087.001	One Thousand AND Eighty-Seven point Zero Zero One	26088.024	Twenty-Six Thousand AND Eighty-Eight point Zero Two Four	I have seen
2	--	N/A	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	Sqm	1453.720	316.001	Three Hundred and Sixteen point Zero Zero One	459376.974	Four Lakh Fifty-Nine Thousand Three Hundred and Seventy-Six point Nine Seven Four	I have seen
3	--	N/A	"safety measure item (gum boot, visible vest, helmet etc) & net (hessian cloth/Fly proof net/safety belt, hand gallops etc) around construction work place (along the height of the building) where public safety is likely to be endangered due to construction activities; which	Item	1.000	12500.001	Twelve Thousand Five Hundred point Zero Zero One	12500.001	Twelve Thousand Five Hundred point Zero Zero One	I have seen

			shall be supported using scaffolding around the building for brick work/ plaster; including fitting and fixing in position providing necessary anchors, wires, ties etc. picking up of unserviceable lagoon surface and removal of debris to a safe distance. all complete and accepted by the Engineer-in-charge. "						
								Grand Total: 497964.999	Four Lakh Ninety- Seven Thousand Nine Hundred and Sixty- Four point Nine Nine Nine

This Priced Bill of Quantities (BOQ) is Electronically Signed by Mr. Nazmul Hasan on behalf of M/s. Nasima Enterprise

M/s. Nasima Enterprise

Tenderer's Quoted Price

Tenderer's Quoted Price

Total Estimated Cost (BDT)	Percentage (-5% to +5%)	Offered Amount (in figures) (BDT)	Offered Amount (in words) (BDT)
497964.999	-5.000	473066.749	Four Lakh Seventy-Three Thousand AND Sixty-Six point Seven Four Nine
	Grand Total:	473066.749	Four Lakh Seventy-Three Thousand AND Sixty-Six point Seven Four Nine

This Tenderer's Quoted Price is Electronically Signed by Mr. Nazmul Hasan on behalf of M/s. Nasima Enterprise