

DHAKA WATER SUPPLY & SEWERAGE AUTHORITY

Office of the Executive Engineer
Civil Maintenance Division
Dhaka WASA, Dhaka
6th floor, WASA Bhaban
98 Kazi Nazrul Islam avenue, Dhaka.

(9)

Name of the Work: Repair and maintenance works of officers quarter building Meghna (unit-501) at Asadgate WASA Compound.

Sl. No.	Item No.	Description of the item	Quantity	Unit	Rate	Amount
1	PWD-22 11.1	Supplying and making door and window frames (Chowkat) for all floors in/c wall side grove cutting, moulding by CNC machine or any other means with matured seasoned wood of required size including painting two coats of coal tar to the surface in contact with wall, fitting and fixing in position etc. all complete and accepted by the Engineer-in-charge. (All sizes of wood are finished).				
	11.1.1	Frame made from seasoned Mehgoni wood (Chemically treated)				
	11.1.1.1	Upto Size 0'-2.5" x 0'-6" (finished)	0.052	cum	135509.000	7046.468
2	PWD-22 12.1	Supplying, fitting and fixing of 38 mm thick well matured seasoned (moisture content should be between 12% to 16%) solid wood single leaf door shutter having stile section 100mm x 38mm, top rail section 125mm x 38mm, lock rail section 100mm x 38mm and bottom rail section 225mm x 38mm (made from minimum 250mm wide plank) with 4nos 100mm long, 3mm thick hinge, 12mm dia 250mm long tower bolt, 12mm dia 200mm long socket bolt, 2nos 150mm long handle, hinged cleats and buffer blocks. All complete in all floors and accepted by the Engineer-in-charge. (All sizes of wood are finished)				
	12.1.1.1	Kathal (SS Fittings)	1.800	sqm	9041.490	16274.682
3	PWD-22 15.1.1	Minimum 12 mm thick cement sand (F.M. 1.2) plaster (1:4) with fresh cement to both inner and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	12.000	sqm	299.000	3588.000
4	PWD-22 16.2.1	Interior standard acrylic emulsion paint (plastic or matt finish) of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container; applying to interior wall and ceiling with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary interior sealer of specified brand on prepared surface; then applying necessary interior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of interior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	25.000	sqm	258.000	6450.000
5	PWD-22 6.6	Supplying, fitting and fixing country made glazed wall tiles complying BDS ISO 13006: 2015, irrespective of color &/or design, with 20 mm thick cement sand (F.M. 1.2) mortar (1:3) base and raking out the joints with white cement including cutting, laying and hire charge of machine and finishing with care etc. including cost of water, electricity and other charges complete in all respect and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M). In ground floor				
	6.6.3	Wall tiles more than 250 mm x 400 mm & less than or equal to 300 mm x 600 mm in sizes	8.050	sqm	1845.000	14852.250
6	M/R	Electrical fitting fixing & line repair.	1.000	Item	1500.000	1500.000
					Total : TK.	49711.400
					Say Total : TK.	49711.000

In word: Forty nine thousand seven hundred eleven taka only

19.07
2024

মোহাম্মদ রিয়াজুল ইসলাম
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।

Rahatun
19.07.24

রাহাত উন নবী
সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।

19.07.24

মুজা সাহা
নির্বাহী প্রকৌশলী
সি এম বিভাগ
ঢাকা ওয়াসা।