



OFFICE OF THE EXECUTIVE ENGINEER
MODS Zone -3, Dhaka WASA,
Lalmatiasteel Tank Compound, DHAKA.

Name of work : Replacement and Repairing of Manhole cover & chamber at Elephant road, West Rajabazar & Indira road under MODS Zone-3, Dhaka WASA.

Sl. No	Basis of rate	Description	Qty.	Unit	Rate (Taka)	Total Amount
1	DWASA C-04.2	Brick works of width one brick or one and a half brick length with first class bricks in cement sand (F.M. 1:2) mortar (1:6) in superstructure including raking out joints, filling the interstices with mortar, cleaning and soaking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7 days etc. all complete (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) and accepted by the Engineer.(Cement: CEM-II/A-M)In ground floor.	1.55	cum	4819.00	7469.45
2	DWASA C-16.10	Renewing plaster in/c damp proof treatment with chemical Desalt S-01 & Foam Lub or equivalent as per specification after stripping off old plaster including cleaning, scaffolding etc. complete as per direction of the Engineer.	20.72	sqm	187.00	3874.64
3	DWASA C-20	Re-Fitting & fixing of manhole cover by cement concrete . Supply will be contractor without CI cover.all complete and accepted by the Engineer	5.00	each	1500.00	7,500.00
4	M/R	Removal of wastage,dismantaliedrock,sewer sludge etc. by auto van.all complete and accepted by the Engineer	5.00	each	1000.00	5,000.00
5	App. rate	Demolition of carpeting, cutting of earth etc. by skilledlabour.all complete and accepted by the Engineer.	10	each	647.00	6,470.00
6	DWASA C 2.8.1	Sand filling in foundation trenches and plinth with sand having F.M. 0.5 to 0.8 in 150mm layers including leveling, watering and compaction to achieve minimum dry density of 90% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only etc. all complete and accepted by the Engineer.	01	Truk	3200.00	3,200.00
7	M/R	Manhole Cleaning by Sewer cleaneretc.all complete and accepted by the Engineer	06	each	1000.00	6,000.00
8	DWASA S-20	Bailing out of all water from pipe line trench with supply of de-watering pump required size including supplying of fuel lubricants and all other required accessories & manpower to keep the trench in a a dry condition at all times etc.	3.00	p/day	1862.00	5,586.00
9	M/R	Safety barricade by bamboo, flag, , lighting etc.all complete and accepted by the Engineer	5	each	700.00	3,500.00
Total					Tk.	48,600.09
Say					Tk.	48,600.00

In word : Taka Forty Eight thousand six hundred only.


16.08.23
অশোক কুমার হালদার
উপ-সহকারী প্রকৌশলী
মডস জোন-৩, ঢাকা ওয়াসা।


16.08.23
মিঃ মজুমদার
কারী প্রকৌশলী
মডস জোন-৩
ঢাকা ওয়াসা।


16.8.23
জয়ন্ত সাহা
নির্বাহী প্রকৌশলী (চঃ দাঃ)
মডস জোন-৩, ঢাকা ওয়াসা।