

SECTION-6: Bill of Quantities

Name of works: Repairing and Raising of Boundary Wall at Kazlarpar-02 & IG Gate Staff Quarter DTW Area Under MODS Zone-1, Dhaka WASA.

IFT No: 46.113.404.00.00.229.2025.34, Date: 24/09/2025


Package No: WR-07(B)-6

Lot No: N/A.

Name of the work: Repairing and Raising of Boundary Wall at Kazlarpar-02 & IG Gate Staff Quarter DTW Area Under MODS Zone-1, Dhaka WASA.

Item No.	Basic of Rate	Item code PWD Rate-2022	Description of Items of works (Specifications Preferably built-in)	Unit	Quantity	Unit rates (In figures) BDT	Amount (In figures) BDT
1		2	3	4	5	6	7
1	PWD Rate-2022	32.1	Stripping of unserviceable plaster including racking out joints, cleaning etc.	sqm	179.256	32.824	5883.899
2	Civil	15.1.1	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to both inner-and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge.	Sqm	211.941	333.523	70687.222
3	Civil	02.10.2	Sand filling in foundation trenches and plinth with sand having minimum F.M. 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge.	cum	32.995	1235.621	40769.244
4	Civil	16.1.2	Exterior premium acrylic emulsion paint of approved best quality and color with high performance against dirt picking tendency and efflorescence resistance properties along with water resistin gproperties and resistance properties against fungi, fading and flaking from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. up to desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge	Sqm	209.231	315.523	66017.319
5	Civil	4.3	Brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:4) in exterior walls including filling the interstices with mortar, raking out joints, cleaning and soaking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7 days etc. all complete including cost of water, electricity and other charges (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) accepted by the Engineer-in-charge. (Cement: CE:M-II/B-M) In ground floor	cum	25.475	10690.705	272347.677

M/s. Rittika Trading
Proprietor



Item No.	Basic of Rate	Item Code PWD Rate-2022	Description of Items of works (Specifications Preferably built-in)	Unit	Quantity	Unit rates (In figures) BDT	Amount (In figures) BDT
1		2	3	4	5	6	7
6	Civil	16.3.1	Standard synthetic enamel paint of approved best quality and colour delivered from authorized local agent of the manufacturer in a sealed container, having high water resistance, high bondability, flexibility property: using specified brand thinner applying to metallic or wooden surface by brass/roller/spray in 2 coats over single coat anti corrosive coating including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, all complete in all floors and accepted by the Engineer-in-charge.	Sqm	7.806	200.114	1562.124
7	Approved Rate		Making Dhaka WASA Monogram (Height of the monogram =0.75m, width =0.50m) out side of boundary wall (alternatively English & Bangali) and painting to Monogram as per Specification & direction of the Engineering in Charge.	Each	16.000	1,588.201	25411.216
8	L/S		Site cleaning work for the removal all unusable materials from the site with contractor own arrangement all complete as per direction of the E/C.	L/S	1.000	15,000.001	15000.001
							497678.703

In Word: Tk. Four Lakh Ninety Seven Thousand Six Hundred And Seventy Eighty Point Seven ~~Zero~~ Three only.

Tender Price Quoted by the Tenderer : The Tenders shall qution in the folling blanks Space.

(496561.54) Tk. in word = Four Lax Ninety-six thousand five hundred sixty-one Point Five four Taka only.
 (Tender Price quoted by the Tenderer: [0.224]% (point two two four percent) above / below / at par the total estimated cost in the BOQ).

Anno

3/3

20/10/25

20/10/25

M/s. Rittika Trading

Proprietor