



Dhaka Water Supply & Sewerage Authority
Office of the Executive Engineer
MODS Zone-1, Dhaka WASA

Name of Work : Repairing & Maintenance of Boundary Wall, Pump House and Toilet at Shamibag and Basabo-2 Sewer Pump Under MODS Zone-1, Dhaka WASA.

Sl. No.	PWD rate Schedule 2014	Description of the Items	Quantity	Unit	Unit rates (in figures) (BDT)	Amount (In Figure) (BDT)
(1)	(2)	(3)	(4)	(5)	(6)	(7)
1	PWD-19.7	Manufacturing, Supplying and fitting-fixing of ordinary type M.S. folding gate with 12mm x 12mm MS square solid bar and 25mm x 25mm x 6mm MS Angle box fram including fabrication, welding, cost of electricity, workshop charge, carriage, cutting grooves, mending good the damages, finishing, curing etc. including fabrication, reveting, welding as and where necessary, etc. all complete as per drawing, design and accepted by the Engineer.	6.9	sqm	4865.00	33568.50
2	PWD-4.3	Brick work with first class bricks in cement sand (F.M.1.2) mortar (1.4) in exterior walls including filling the interstices with mortar, raking out joints, cleaning and socking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7 days etc. all complete including cost of water electricity and other charges (measurement to given as 250 mm width for one brick legth and 375 mm for one bricks and a half bricks length) accepted by the Engineer.	5.75	cum	6013.00	34574.75
3	PWD-15.2	Minimum 12 mm thick cement sand (F.M. 1.2) plaster with neat cement finishing to plinth wall (1:4) with cement up to 150 mm below ground level with neat cement finishing including washing of sand, finishing the edges and corners and curing atleast for 7 days, cost of water, electricity and other charges etc. all complete in all respect as per drawing and accepted by the Engineer. (Cement: CEM-II/A-M) Ground floor	66.0	Sqm	246.00	16236.00
4	PWD-21.3	Manufacturing, supplying, fitting and fixing M.S. grill fencing as per design withouter frames having 38 x 38 x 6 mm M.S. angle and innermembers having 6 mm dia M.S. rod placed @ 110 mm c/c diagonally on both direction, welding each crisscrossend of rod with corners of outer frame including cutting rods and size angles to required shapes and size and setting the entire fence with the previously installed tube (angle box) post including thorough and full welding the frame with the angle box posts, painting 2 coats of synthetic enamel paint over a coat of anticorrosive priming etc. all complete as per drawing and accepted by the Engineer. (Rate is excluding the cost of angle box post and its installation and excluding the cost of paint)	38.70	sqm	2238.00	86610.60






Sl. No.	PWD rate Schedule 2014	Description of the Items	Quantity	Unit	Unit rates (in figures) (BDT)	Amount (In Figure) (BDT)
(1)	(2)	(3)	(4)	(5)	(6)	(7)
5	PWD-Extra Item	Construction of 125 mm thick boundary wall with 250 mm x 250 mm size brick pillar @ 2.44 meter c/c, of height 1.52 meter above G.L and 0.76 m below G.L and RCC (f _c = 19 MPa, minimum f _{cr} = 24 MPa in nominal mix 1: 2:4) coping of 90 mm thick and 375 mm width, 12 mm thick plaster (1:6) in both sides of the wall including the cost of reinforcement and whitewashing etc.	5.2	rm	6890.71	35831.69
8	Market Prise	Bearing as per sample(Main gate)	6.0	Nos	1200.00	7200.00
10	Market Prise	Water Tap (SS)	4.0	Nos	580.00	2320.00
11	Market Prise	56"Celling Fan	2.0	Nos	3250.00	6500.00
12	Market Prise	LED Bulb18-30w	6.0	Nos	350.00	2100.00
13	C12-208	38 mm dia G.I Pipe	32.0	rft	140.00	4480.00
14	Market Prise	Electrical Cable. 1X25rm(7-w)	3.0	Coile	4644.00	13932.00
15	PWD-16.6	Painting to door and window frames and shutters in two coats approved best quality and color of synthetic enamel paints delivered from authorized local agent of the manufacture in a sealed container, having highly water resistat, high bondibilty, flexible, using specific brand thinner applied by brass/roller/spray over a coat of primeing elapsing time for drying including surface cleaning from dust, oil ordirt,smootheningdirt,smoothening ,finishing and polishing with sand paper and nessary tools, scaffolding testing charges etc. all complete in all floors approved by the Engineer.	24.00	sqm	183.00	4392.00
16	PWD-16.8.1	Plastic emulsion paint Approved best quality and colour delivered from athorized local agent of the manufactor in a sealed container, applying to wall and celling in 2 coats over a coat of brand specifiedprime or seale elapsing specified time for drawing/ recoating matt finish including cleaning and sand papering making the surface free from loose and flaky materials, dirt grease, wax, polish, scraping all chalked and scaled materials, applying the paint by brashing/rollar and necessary scaffolding etc. all complete in all floors accepted by the Engineer.	240.00	sqm	159.00	38160.00
17		All Side Cleaning, Fitting and Fixing Charge	1.0	Item	12000.00	12000.00
Total Tk =						297905.54

In word : Two Lac Ninty Seven Thousand Nine Hundared Five Point Five Four Taka Only.


 07/08/23
 Subroto Kumar Deb
 Sub-Assistant Engineer
 MODS Zone-1, Dhaka WASA


 07.08.23
 Md. Emdadul Haque
 Assistant Engineer
 MODS Zone-1, Dhaka WASA


 7/8/23
 Md. Al Amin
 Executive Engineer
 MODS Zone-1, Dhaka WASA