


Dhaka Water Supply and Sewerage Authority
Office of the Executive Engineer
Meter Division
4/4, Shegunbagicha, Dhaka

Name of work: Rising, Plastering, Painting and necessary Repair works of existing Boundary Wall at Meter Division Compound, Segunbagicha, Dhaka.

Sl. No.	PWD, 2022	Description of the item	Quantity	Unit	Rate	Amount
1	04.3	Brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:4) in exterior walls including filling the interstices with mortar, raking out joints, cleaning and soaking the bricks at least for 24 hours before use and washing of sand, necessary scaffolding, curing at least for 7 days etc. all complete including cost of water, electricity and other charges (measurement to given as 250 mm width for one brick length and 375 mm for one brick and a half brick length) accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor	1.500	cum	8419.001	12628.502
2	04.16	125 mm brick works with first class bricks with cement sand (F.M. 1:2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days in all floors including cost of water, electricity and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) In ground floor	78.750	sqm	1185.001	93318.829
3	15.1.2	Minimum 12 mm thick cement sand (F.M. 1:2) plaster (1:4) with fresh cement to outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) ground floor.	240.000	sqm	316.001	75840.240
4	16.1.1	Exterior standard acrylic emulsion paint of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation including cleaning, drying, making free from dirt, grease, wax, removing all chalked and scaled materials, fungus, mending good the surface defects using sand paper and necessary scaffolding; applying necessary exterior sealer of specified brand on prepared surface; then applying necessary exterior putty of specified brand for levelling, spot filling, crack filling and cutting by sand paper/zero water paper; finally applying 2 coats of exterior emulsion paint spreading by brush/roller/spray & necessary scaffolding etc. upto desired finishing, elapsing specified time for drying or recoating; all complete in all floors and accepted by the Engineer-in-charge.	337.500	sqm	274.001	92475.338
5	21.8	Supplying, fitting and fixing 12 BWG barbed wire (2 ply, 4 points) in fencing work @ 150 mm c/c both horizontally and vertically, supported by 38 mm x 38 mm x 6 mm M.S. Y-shape angle post (300 mm embedded in R.C.C. or in brick work with a cement concrete base of 75 mm x 75 mm x 300 mm) 600 mm vertical and 450 mm inclined or as per requirement @ 2.4 m c/c including straightening, binding the joints with 18 BWG wire, making holes in the angle etc. including supplying all necessary materials complete in all respect and accepted by the Engineer-in-charge. (Rate is excluding the cost of paint, R.C.C /brick work or C.C. which is to be paid as per corresponding items in the schedule).	66.400	sqm	1034.001	68657.666
					Total Tk.	342920.58
					Say Total Tk.	342921

In Word: Three Lakh Forty Two Thousand Nine Hundred Twenty One Taka Only


17.07.2023
ওবায়দুর রহমান
উপ-সহকারী প্রকৌশলী
মিটার বিভাগ, ঢাকা ওয়াশা


17.07.2023
মোঃ মাহবুব হাসান
নির্বাহী প্রকৌশলী
মিটার বিভাগ
ঢাকা ওয়াশা।