

**Office of the Executive Engineer
MODS Zone-8, Dhaka WASA
Natun Bazar Buster Pump Compound, Baridhara, Dhaka.**

Name of Works : Repairing Of HDPE Water Line Leakage & Removal dirty Water Of 9/2 Kazi Sarani Road Purbo Badda (DMA-805) under MODS Zone-8, Dhaka WASA.

Sl. No.	Basis of Rate	Description Of Item	Quantity	Unit	Rate (Tk.)	Amount (Tk.)	Remarks
1	Approved Rate	75 mm dia HDPE Pipe	3.00	P/M			Supply by Sub store
2	Approved Rate	160 mm dia HDPE Pipe	6.00	P/M			Supply by Sub store
3	Approved Rate	75 mm dia HDPE Sleeve E.F	2.00	Nos			Supply by Sub store
4	Approved Rate	160 mm dia HDPE Sleeve E.F	4.00	Nos			Supply by Sub store
7	Approved Rate	Excavation and removal of soil from the trench bottom beyond allowable depth in accordance with the technical specification and direction of Engineering in charge,	35.600	Cum	331.000	11783.600	
8	Approved Rate	supply depositing and compaction of fine sand back filling (FM 0.8) at all required depth in accordance with the technical specification and direction of Engineering in charge, and standard detail drawings for all water pipe line diameters.	34.500	Cum	578.000	19941.000	
9	PWD soR 2022 (Revised) (03.1.1)	One layer brick flat soling in foundation with first class/picked jhama bricks (BDS 208) including preparation of bed and filling the interstices with local sand, leveling etc.	15.000	p/sqm	636.001	9540.015	
10	Approved Rate	Skilled Technician	3.00	P/Person	1000.00	3,000.00	
11	Approved Rate	Labour Charge	5.000	P/Person	800.000	4000.000	
Total=						48264.615	

In words: Forty Eight Thousand Two Hundred Sixty Four point Six One Five Tk Only.

Read
16.08.26
আবদুল্লাহ আলি মনির
উপ-সহকারী প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াসা।

Quon
16.08.26
মোঃ গোলাম মোস্তফা খানকার
উপ-বিত্তীয় প্রকৌশলী
মডস জোন-৮, ঢাকা ওয়াসা।

26/08/2026
অনুপম কুমার মন্ডল
নির্বাহী প্রকৌশলী
মডস জোন-৮
ঢাকা ওয়াসা।