

Dhaka Water Supply and Sewerage Authority

Office of the Executive Engineer

Civil Maintenance Division

6th Floor, WASA Bhaban, Kawranbazar

98, Kazi Nazrul Islam Avenue, Dhaka-1215.

Name of work: Replacement & cleaning of Sewer line with ancillary works at Narinda Central Sewer pump staff quarter compound, Dhaka WASA.

Estimate							
SL No.	Group	PWD-2022 Item Code	Description	Unit	Quantity	Unit Rate	Amount(Tk)
1	Civil	26.44.1	Supplying and laying uPVC pipe for for underground including fitting, fixing etc. all complete approved and accepted by the Engineer-in-charge.150 mm dia with wall thickness 4.5 mm - 6.6 mm uPVC pipe	m	19.207	1,416.001	27197.131
2	Civil	27.3.5	38/ 40 mm dia uPVC socket adapter	each	9.000	132.001	1188.009
3	-	13	Plumber	each	7.000	700.001	4900.007
4	-	28	Sweeper for ODD Job	each	8.000	800.000	6400.000
5	Civil	03.4.2	Lean / blinding concrete (1:3:6) in foundation or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge.(Cement: CEM-II/B-M).Lean / blinding concrete in floor (1:3:6) with cement, brick chips and sand of F.M. 1.2	cum	1.247	7729.001	9638.064
						Total (Tk.)	49323.211
						Say Total(Tk.)	49,323

IN WORD: FORTY NINE THOUSAND THREE HUNDRED TWENTY THREE TAKA ONLY

Ruby
20.09.26

রাফেজ আহমেদ
উপ-সহকারী প্রকৌশলী
সি এম বিভাগ
ঢাকা গুলশান।

Ruby
20.09.26
মুজা সাহা
নির্বাহী প্রকৌশলী
সিএম বিভাগ
ঢাকা ওয়ার্ড